



UNH-IOL MIPI Alliance Test Program D-PHY RX Conformance Test Report

InterOperability Lab — 21 Madbury Road, Suite 100 — Durham, NH 03824 — (603) 862-3749

22-Jul-2016

Engineer Name
Sample Company, Inc.
1010 Mobile Way
San Jose, CA 95101

Mr. Engineer:

Enclosed are the test results from the D-PHY RX Physical Layer Conformance testing performed on the:

Sample Company 1234 Camera Sensor 1-Lane CSI-2 Transmitter

The testing was performed according to v1.2 of the MIPI Alliance D-PHY Physical Layer Conformance Test Suite, which is available to MIPI Alliance Members at:

<https://members.mipi.org/wg/All-Members/home/approved-specs>

Any issues observed during testing are listed below:

- **NO CONFORMANCE ISSUES WERE OBSERVED FOR ANY OF THE PERFORMED TESTS**

Please feel free to contact me at kerry.munson@iol.unh.edu with any questions you may have regarding this report.

Sincerely,

A handwritten signature in blue ink that reads "Kerry Munson". The signature is written in a cursive, flowing style.

Kerry Munson

Digital Signature Information

This document was created using an Adobe digital signature. A digital signature helps to ensure the authenticity of the document, but only in this digital format. For information on how to verify the integrity of this document, please proceed to the following site:

<https://www.iol.unh.edu/testing/reports/validation>

If, after following the steps indicated above, the document status still indicates “Validity of author NOT confirmed”, please contact the UNH-IOL to confirm the document’s authenticity. To further validate the certificate integrity, Adobe 6.0 should report the following fingerprint information:

MD5 Fingerprint (2016): 3996 A48C 02E0 38DA F7AB E1ED BDE9 B5F0
SHA-1 Fingerprint (2016): 41EE 65F4 8A6A 3AA6 3DAF 63F4 787D 977B 4849 C9DD



Table 1-0: Test Setup and DUT Configuration Information


DUT Details	
Week testing was performed	20160722
Manufacturer	Sample Company
Model	1234 Camera Sensor
Number of HS Data Lanes	1 Data Lane
Max. Supported HS Bit Rate	2500 Mbps
Tested HS Bit Rate	2500 Mbps
Environmental Temperature	Room Temperature ~25 C (Tnom)
UNH-IOL ID Number	99999
Test System Hardware	
Real-time DSO	Agilent Infiniium DSA91304A, 13GHz, 40GS/s Real-time DSO
Signal Generator	Agilent ParBERT (Test 2.1.6, Group2, Test 2.4.1, Test 2.4.6) Introspect SV3C (Used for tests not performed with Agilent ParBERT)
Additional Comments/Notes	
 The logo for the University of New Hampshire InterOperability Laboratory (UNH IOL) is centered in the 'Additional Comments/Notes' section. It features a stylized sun with rays above the letters 'IOL', which are enclosed within a large, light-colored oval.	

Table 2-1: (Section 2, Group 1): LP-RX Voltage and Timing Requirements

Test/Parameter	Conformance Range	Measured (Clock/Data 0)	Units
Test 2.1.1: LP-RX Logic 1 Input Voltage (V_{IH})			
Minimum voltage level where LP receiver consistently detects Logic 1	≤ 880 ($\leq 1.5\text{Gbps}$) ≤ 740 ($> 1.5\text{Gbps}$)	776	mV
Test 2.1.2: LP-RX Logic 0 Input Voltage, Non-ULP State (V_{IL})			
Maximum voltage level where non-ULP LP receiver consistently detects Logic 0	≥ 550	653	mV
Test 2.1.3: LP-RX Logic 0 Input Voltage, ULP State ($V_{IL-ULPS}$)			
Maximum voltage level where ULP-mode LP receiver consistently detects Logic 0	> 300	N/P	mV
Test 2.1.4: LP-RX Input Hysteresis (V_{HYST})			
Maximum Logic 1 hysteresis	> 25	12	mV
Test 2.1.5: LP-RX Minimum Pulse Width Response (T_{MIN-RX})			
Minimum detected LP pulse width	< 20	10	ns
Test 2.1.6: LP-RX Input Pulse Rejection (e_{SPIKE})			
Maximum tolerated $-e_{SPIKE}$ while in Logic 1 state	> 300	510	mV*ps
Maximum tolerated $+e_{SPIKE}$ while in Logic 0 state	> 300	510	mV*ps
Test 2.1.7: LP-RX Interference Tolerance (V_{INT} and f_{INT})			
Device tolerates all interference test cases	Pass/Fail	PASS	-
Test 2.1.8: LP-CD Logic Contention Thresholds (V_{IHCD} and V_{ILCD})			
Measured V_{IHCD} voltage	> 450	N/A*	mV
Measured V_{ILCD} voltage	< 200	N/A*	mV

* Test is Not Applicable because the DUT does not support bidirectional operation

Table 2-2: (Section 2, Group 2): LP-RX Behavioral Requirements

Test/Parameter	Conformance Range	Measured	Units
Test 2.2.1: LP-RX Initialization period (T_{INT})			
Minimum T_{INT} that causes the DUT to successfully receive data	> 1	PASS	ms
Test 2.2.2: ULPS Exit: LP-RX T_{WAKEUP} Timer Value			
Verify that the DUT can successfully receive image data following a 1ms T_{WAKEUP} interval	Pass/Fail	PASS	-
Test 2.2.3: Clock Lane LP-RX Invalid/Aborted ULPS Entry			
Verify that DUT operation is not affected by invalid Clock Lane ULPS Entry sequence #1 (LP-11/10/11)	Pass/Fail	PASS	-
Verify that DUT operation is not affected by invalid Clock Lane ULPS Entry sequence #2 (LP-11/10/01/11)	Pass/Fail	PASS	-
Test 2.2.4: Data Lane LP-RX Invalid/Aborted Escape Mode Entry			
Verify that DUT operation is not affected by invalid Escape Mode Entry sequence #1 (LP-11/10/00/01/11)	Pass/Fail	PASS	-
Verify that DUT operation is not affected by invalid Escape Mode Entry sequence #2 (LP-11/10/00/11/11)	Pass/Fail	PASS	-
Verify that DUT operation is not affected by invalid Escape Mode Entry sequence #3 (LP-11/10/11/11/11)	Pass/Fail	PASS	-
Test 2.2.5: Data Lane LP-RX Invalid/Aborted Escape Mode Command			
DUT successfully ignores Test Case #1	Pass/Fail	PASS	-
DUT successfully ignores Test Case #2	Pass/Fail	PASS	-
DUT successfully ignores Test Case #3	Pass/Fail	PASS	-
DUT successfully ignores Test Case #4	Pass/Fail	PASS	-
DUT successfully ignores Test Case #5	Pass/Fail	PASS	-
DUT successfully ignores Test Case #6	Pass/Fail	PASS	-
DUT successfully ignores Test Case #7	Pass/Fail	PASS	-
DUT successfully ignores Test Case #8	Pass/Fail	PASS	-
DUT successfully ignores Test Case #9	Pass/Fail	PASS	-
DUT successfully ignores Test Case #10	Pass/Fail	PASS	-
DUT successfully ignores Test Case #11	Pass/Fail	PASS	-
DUT successfully ignores Test Case #12	Pass/Fail	PASS	-
DUT successfully ignores Test Case #13	Pass/Fail	PASS	-
DUT successfully ignores Test Case #14	Pass/Fail	PASS	-
DUT successfully ignores Test Case #15	Pass/Fail	PASS	-
Test 2.2.6: Data Lane LP-RX Escape Mode Invalid Exit (INFORMATIVE)			
Observe DUT behavior for Test Case #1 (Mark-0/Stop)	(Informative)	PASS	-
Observe DUT behavior for Test Case #2 (Space/Stop)	(Informative)	PASS	-
Observe DUT behavior for Test Case #3 (Stop/Stop)	(Informative)	PASS	-
Test 2.2.7: Data Lane LP-RX Escape Mode, Ignoring of Post-Trigger-Command Extra Bits			
DUT successfully ignores Test Case #1 (Reset-Trigger+ULPS)	Pass/Fail	PASS	-
DUT successfully ignores Test Case #2 (Unknown-3+ULPS)	Pass/Fail	PASS	-
DUT successfully ignores Test Case #3 (Unknown-4+ULPS)	Pass/Fail	PASS	-
DUT successfully ignores Test Case #4 (Unknown-5+ULPS)	Pass/Fail	PASS	-
Test 2.2.8: Data Lane LP-RX Escape Mode Unsupported/Unassigned Commands			
DUT successfully ignores all Test Cases (248 Unassigned codes, and also Undefined-1, Undefined-2, Unknown-3, Unknown-4, Unknown-5)	Pass/Fail	PASS	-

Table 2-3: (Section 2, Group 3): HS-RX Voltage and Timing Requirements

Test/Parameter	Conformance Range	Measured (Clk/Data/Data1)	Units
Test 2.3.1: HS-RX Common Mode Voltage Tolerance ($V_{CMRX(DC)}$)			
DUT successfully receives Test Case #1 (70/440)	Pass/Fail	PASS	-
DUT successfully receives Test Case #2 (70/140)	Pass/Fail	PASS	-
DUT successfully receives Test Case #3 (330/520)	Pass/Fail	PASS	-
DUT successfully receives Test Case #4 (330/140)	Pass/Fail	PASS	-
Test 2.3.2: HS-RX Differential Input High Threshold (V_{IDTH})			
Minimum V_{IDTH} where the DUT does not indicate errors	< 70 (<= 1.5 Gbps) < 40 (> 1.5 Gbps)	35	mV
Test 2.3.3: HS-RX Differential Input Low Threshold (V_{IDTL})			
Maximum V_{IDTL} where the DUT does not indicate errors	> -70 (<= 1.5 Gbps) > -40 (> 1.5 Gbps)	-35	mV
Test 2.3.4: HS-RX Single-Ended Input High Voltage (V_{IHHS})			
DUT successfully receives Test Case #1 (325/540)	Pass/Fail	PASS	-
Test 2.3.5: HS-RX Single-Ended Input Low Voltage (V_{ILHS})			
DUT successfully receives Test Case #1 (95/540)	Pass/Fail	PASS	-
Test 2.3.6: HS-RX Common-Mode Interference 50MHz - 450MHz ($\Delta V_{CMRX(LF)}$)			
DUT successfully receives Test Case #1 (200/400)	Pass/Fail	PASS	-
Test 2.3.7: HS-RX Common-Mode Interference Beyond 450MHz ($\Delta V_{CMRX(HF)}$)			
DUT successfully receives Test Case #1 (200/400)	Pass/Fail	PASS	-
Test 2.3.8: HS-RX Setup/Hold and Jitter Tolerance			
(Minimum V_{OD}): DUT successfully receives minimum T_{HOLD}	Pass/Fail	PASS	-
(Minimum V_{OD}): DUT successfully receives minimum T_{SETUP}	Pass/Fail	PASS	-
(Nominal V_{OD}): DUT successfully receives minimum T_{HOLD}	Pass/Fail	PASS	-
(Nominal V_{OD}): DUT successfully receives minimum T_{SETUP}	Pass/Fail	PASS	-

Table 2-4: (Section 2, Group 4): HS-RX Timer Requirements

Test/Parameter	Conformance Range		Measured	Units
	Formula	Numeric		
Test 2.4.1: Data Lane HS-RX $T_{D-TERM-EN}$ Value				
(Data Lane 0): Minimum $T_{D-TERM-EN}$	$< 35+4*UI$	< 36.6	35.1	ns
(Data Lane 1): Minimum $T_{D-TERM-EN}$	$< 35+4*UI$	< 36.6	N/P	ns
(Data Lane 2): Minimum $T_{D-TERM-EN}$	$< 35+4*UI$	< 36.6	N/P	ns
(Data Lane 3): Minimum $T_{D-TERM-EN}$	$< 35+4*UI$	< 36.6	N/P	ns
Test 2.4.2: Data Lane HS-RX $T_{HS-PREPARE} + T_{HS-ZERO}$ Tolerance				
DUT successfully receives Test Case #1	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #2	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #3	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #4	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #5	-	Pass/Fail	PASS	-
Test 2.4.3: Data Lane HS-RX $T_{HS-SETTLE}$ Value				
Measured $T_{HS-SETTLE}$	$> 85+6*UI$	> 87.4	N/P*	ns
Test 2.4.4: Data Lane HS-RX $T_{HS-TRAIL}$ Tolerance				
DUT successfully receives Test Case #1 (80ns+4*UI)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #2 (40ns+4*UI)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #3 (70ns+12*UI)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #4 (105ns+12*UI)	-	(Informative)	N/P	-
Test 2.4.5: Data Lane HS-RX $T_{HS-SKIP}$ Value				
Measured $T_{HS-SKIP}$	40 / 55+4*UI	40 / 56.6	PASS	ns
Test 2.4.6: Clock Lane HS-RX $T_{CLK-TERM-EN}$ Value				
Measured $T_{CLK-TERM-EN}$	-	< 38	30.5	ns
Test 2.4.7: Clock Lane HS-RX $T_{CLK-PREPARE} + T_{CLK-ZERO}$ Tolerance				
DUT successfully receives Test Case #1 (70/300)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #2 (38/332)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #3 (38/262)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #4 (95/275)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #5 (95/205)	-	Pass/Fail	PASS	-
Test 2.4.8: Clock Lane HS-RX $T_{CLK-SETTLE}$ Value				
Measured $T_{CLK-SETTLE}$	-	> 95	N/P*	ns
Test 2.4.9: Clock Lane HS-RX $T_{CLK-TRAIL}$ Tolerance				
DUT successfully receives Test Case #1 (80ns)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #2 (40ns)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #3 (70ns+12*UI)	-	Pass/Fail	PASS	-
DUT successfully receives Test Case #4 (105ns+12*UI)	-	(Informative)	N/P	-
Test 2.4.10: Clock Lane HS-RX $T_{CLK-MISS}$ Value				
Measured $T_{CLK-MISS}$	-	< 60	PASS	ns
Test 2.4.11: Clock Lane HS-RX $T_{CLK-PRE}$ and $T_{CLK-POST}$ Tolerance				
DUT successfully receives Test Case #1 (Minimum $T_{CLK-PRE/POST}$)	-	Pass/Fail	PASS	-