

OFA Interoperability Working Group

OFA-IWG Interoperability Test Plan Release 1.10



April 10, 2007
DRAFT

Copyright © 2007 by OpenFabrics - All rights reserved.

This document contains information proprietary to OpenFabrics. Use or disclosure without written permission from an officer of the OpenFabrics is prohibited.

Revision History

Revision	Release Date	
0.50	Apr 4, 2006	First FrameMaker Draft of the Interop Test Plan which was used in the March 2006 IBTA-OpenFabrics Plugfest.
0.51	Apr 25, 2006	Added DAPL and updated MPI.
0.511	June 1, 2006	Arkady Added iWARP.
0.52	May 30, 2006	Added Intel MPI.
0.53	June 6, 2006	Updated uDAPL section provided by Arkady.
0.54	June 13, 2006	Updated entire Test Spec based on changes made by Arkady to incorporate iWARP into the Test Spec.
0.80	June 14, 2006	Updated for the OFA conference in Paris and for BoD meeting. Added OFA logo and URL.
1.0	June 21, 2006	Released after review and approval at the OFA conference in Paris.
1.01	Aug 17, 2006	Updated the iWARP Equipment requirements in the General System Setup section.
1.02	Oct 31, 2006	Updated Table 4 for iSER, Table 5 for SRP, Table 10 for uDAPL and corresponding info in Tables 17,18 and 22 as per request by Arkady. Added new test section from Bob Jaworski for Fibre Channel Gateway.
1.03	Dec 10, 2006	Updated test procedures based on the October 2006 OFA Interop Event. Updated Fibre Channel Gateway test based on changes submitted by Karun Sharma (QLogic). Added Ethernet Gateway test written by Karun Sharma (QLogic).
1.04	Mar 6, 2007	Updated test procedures in preparation for the April 2007 OFA Interop Event
1.05	Mar 7, 2007	Updated iWARP test procedures based on review by Mikkell Hagen of UNH-IOL. Added missing results tables.
1.06	April 3, 2007	Updated for April 2007 Interop Event based on review from OFA IWG Meeting on 3/27/07.
1.07	April 3, 2007	Updated for April 2007 Interop Event based on review from OFA IWG Meeting on 4/3/07
1.08	April 4, 2007	Added list of Mandatory Tests for April 2007 Interop Event.
1.09	April 9, 2007	Updated Intel MPI based on review by Arlin Davis.
1.10	April 10, 2007	Updated after final review by Arlin Davis and after the OFA IWG meeting on 4/10/2007

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

LEGAL DISCLAIMER

"This version of a proposed OpenFabrics Interop Test Plan is provided "AS IS" and without any warranty of any kind, including, without limitation, any express or implied warranty of non-infringement, merchantability or fitness for a particular purpose.

In no event shall OpenFabrics, IBTA or any member of these groups be liable for any direct, indirect, special, exemplary, punitive, or consequential damages, including, without limitation, lost profits, even if advised of the possibility of such damages."

Conditional text tag *Explanation* is shown in green.

~~Conditional text tag Deleted is shown in red with strike through.~~

Conditional text tag *Proposal* is shown in turquoise (r0_g128_b128).

Conditional text tag *Author* is shown as is.

Conditional text tag Comment is shown in red with underline

1 INTRODUCTION

Server OEM customers have expressed the need for RDMA hardware and software to interoperate.

Specifically, InfiniBand HCA, OpenFabrics host software to interoperate with InfiniBand Switches, gateways, and bridges with management software provided by OEMs, and IB integrated server OEM vendors. And, iWARP RNIC and OpenFabrics host software to interoperate with Ethernet Switches and management software and hardware provided by Ethernet Switch OEMs and iWARP integrated server OEM vendors.

It is necessary that the interoperability test effort be an industry-wide effort where interoperability testing is conducted under the auspices of the appropriate networking organizations. For InfiniBand it is IBTA, specifically within the charter of the CIWG. And for iWARP it is IETF, and specifically within UNH IOL iWARP Consortium.

1.1 PURPOSE

This document is intended to describe the production tests step by step explaining each test and its references. The purpose of this test plan is three fold:

- 1) Define the scope, equipment and software needs, and test procedures for verifying full interoperability of RDMA HW and SW. For Infiniband HW it is InfiniBand HCAs using the latest OpenFabrics IB OFED software with currently available OEM Switches and their management software. The target OEM IB Switch vendors are Cisco, Flextronics, QLogic and Voltaire. For iWARP HW it is iWARP RNICs using the latest OpenFabrics OFED software with currently available OEM Ethernet Switches, Bridges, Gateways, Edge Devices and so on with their management software.
- 2) Serve as a basis for evaluating customer acceptance criteria for OFA host software interoperability and OFA Logo.
- 3) Serve as a basis for extensions to InfiniBand IBTA CIWG test procedures related to interoperability and use of these test procedures in upcoming PlugFest events organized by IBTA.

Serve as a basis for extensions to iWARP test procedures for OpenFabrics software related to interoperability and use of these test procedures in upcoming PlugFest events organized by UNH IOL iWARP Consortium.

1.2 INTENDED AUDIENCE

The following are the intended audience for this document:

- 1) Project managers in OEM Switch, Router, Gateway, Bridge Vendor companies to understand the scope of testing and participate in the extension of this test plan and procedures as necessary to meet their requirements.
- 2) IBTA and CIWG, and iWARP and UNH IOL iWARP testing personnel and companies to evaluate the scope of testing and participate in the extension of this test plan and procedures as necessary to meet their requirements.

- 3) Test engineering and project leads and managers who will conduct the testing based on this document.
- 4) Customers and users of OFA host software who rely on OFA Logo for interoperability.
- 5) Integrators and OEM of RDMA products.

1.3 TEST OVERVIEW

The tables below list all required tests for the procedures

Table 1 - IB Link Initialize

Test #	Test	Description Overview
1	Phy link up all ports	Check that all relevant green LEDs are on for all HCAs and switches.
2	Logical link up all ports switch SM	All vendors should check that the link state is up and the port width is 4X.
3	Logical link up all ports HCA SM	All vendors should check that the link state is up and the port width is 4X.

Table 2 - IB Fabric Initialization

Test #	Test	Description Overview
1	Fabric Initialization	Run SM from each node in cluster and see that all ports are in Armed or Active state.

Table 3 - IB IPoIB Tests

Test #	Test	Description Overview
1	Ping all to all	Run SM from one of the nodes and check all nodes responding. Repeat with all SMs.
2	Connect disconnect host	Run SM from one of the nodes and check all nodes responding.
3	FTP Procedure	Using a 4MB test file, put the file, then get the file and finally compare the file.

Table 4 - TI iSER Tests

Test #	Test	Description Overview
1	Basic dd application	Run basic dd application from iSER host connected to target.
2	IB SM kill	[IB Specific] - Kill the IB master SM while test is running and check that it completes properly.
3	Disconnect Initiator	Unload iSER Host and check iSER connection properly disconnected.
4	Disconnect Target	Unload iSER Target and check iSER connection properly disconnected.

Table 4 - TI iSER Tests

Test #	Test	Description Overview
5	Repeat with previous SM Slave	[IB Specific Test] Repeat steps 1-4 now with the previous slave SM (we did not actually stop the target).

Table 5 - IB SRP Tests

Test #	Test	Description Overview
1	Basic dd application	Run basic dd application from SRP host connected to target.
2	IB SM kill	Kill the IB master SM while test is running and check that it completes properly.
3	Disconnect Host	Unload SRP Host and check SRP connection properly disconnected.
4	Disconnect Target	Unload SRP Target and check SRP connection properly disconnected.

Table 6 - TI SDP Tests

Test #	Test	Description Overview
1	netperf procedure	Run netperf where message size is 10, 100, 1000, 10000 and local buffer size is 1024, 6000.
2	FTP procedure	Using a 4MB test file, put the file, then get the file and finally compare the file.
3	IB SCP Procedure	Connect via SCP on IPoIB address from all other nodes uploading and downloading a file.
4	iWARP SCP Procedure	Connect via SCP from all other nodes uploading and downloading a file.

Table 7 - IB SM Tests

Test #	Test	Description Overview
1	Basic sweep test	verify that all SMs are NOT ACTIVE (after receiving the SMSet of SMInfo to DISABLE) and that the selected SM (SM1) is the master (
2	SM Priority test	Verify Subnet and SMs behavior according to the SMs priority.
3	Failover - Disable SM1	Disable the master SM and verify that standby SM becomes master and configures the cluster.
4	Failover - Disable SM2	Disable the master SM and verify that standby SM becomes master and configures the cluster.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

Table 8 - TI MPI - OSU

Test #	Test	Description Overview
1	Test 1: PingPong	
2	Test 1: PingPing point-to-point	
3	Test 2: PingPong	
4	Test 2: PingPing	
5	Test 2: Sendrecv	
6	Test 2: Exchange	
7	Test 2: Bcast	
8	Test 2: Allgather	
9	Test 2: Allgatherv	
10	Test 2: Alltoall	
11	Test 2: Reduce	
12	Test 2: Reduce_scatter	
13	Test 2: Allreduce	
14	Test 2: Barrie	

Table 9 - TI MPI - Intel MPICH2 Suite Description - (Not part of OFA Stack)

Test #	MPICH2 (16 sections, 290 tests)	Intel - MPICH2 Test Suite Section Description
1	attr	Test programs for attribute routines
2	coll	Test programs for various collective operations
3	comm	Test programs for communicator operations
4	datatype	Test programs for various datatype operations
5	errhan	Test programs for error handling operations
6	group	Test programs for the group operations
7	info	Test programs for varios info operations
8	init	Test programs for init operations
9	pt2pt	Test programs for various point to point routines (send, isend, probe, etc.)

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

Table 9 - TI MPI - Intel MPICH2 Suite Description - (Not part of OFA Stack)

Test #	<i>MPICH2 (16 sections, 290 tests)</i>	<i>Intel - MPICH2 Test Suite Section Description</i>
10	rma	Test programs for memory access operations
11	spawn	Test programs for comm_spawn, intercom operations
12	topo	Test programs for various topology routines
13	io	Test programs for file i/o read/write, sync and async
14	F77	Test programs for f77
15	cxx	Test programs for c++
16	threads	Test programs for treaded send/recv

Table 10 - TI MPI - IntelMPITest Suite Description - (Not part of OFA Stack)

Test #	<i>IntelMPITEST (5 sections, 1371 tests)</i>	<i>IntelMPITest Suite Description</i>
1	testlist2l (1085 tests)	c - blocking, coll, datatype, env, group, misc, non-blocking
2	testlist2-2l (23 tests)	c, fortran – datatype create
3	testlist4 (216 tests)	fortran – grp, topo, blocking, coll, datatype, non-blocking, persist, probe, send/recv
4	testlist4lg (1 test)	c - collective overlap
5	testlist6 (46 tests)	c, fortran – topo cart/graph

Table 11 - TI uDAPL

Test #	<i>Test</i>	<i>Description Overview</i>
1	Point-to-Point Topology	Connection and simple send receive.
2	Point-to-Point Topology	Verification, polling and scatter gather list.
3	Switched Topology	Verification and private data.
4	Switched Topology	Add multiple endpoints, polling, and scatter gather list.
5	Switched Topology	Add RDMA Write.
6	Switched Topology	Add RDMA Read.
7	Multiple Switches	Multiple threads, RDMA Read, and RDMA Write.
8	Multiple Switches	Pipeline test with RDMA Write and scatter gather list.
9	Multiple Switches	Pipeline with RDMA Read.
10	Multiple Switches	Multiple switches.

Table 12 - iWARP Connections

Test #	Test	Description Overview
1	UNH iWARP interop tests group 1	Verify that each single iWARP operation over single connection works.
2	UNH iWARP interop tests group 2	Verify that multiple iWARP operations over a single connection work.
3	UNH iWARP interop tests group 3	Verify that multiple iWARP connections work.
4	UNH iWARP interop tests group 4	Verify that disconnect/reconnect physical connections work.
5	UNH iWARP interop tests group 5	Verify that IP Speed negotiation work.
6	UNH iWARP interop tests group 6	Verify that iWARP error ratio work.
7	UNH iWARP interop tests group 7	Verify that stress pattern over iWARP work.
8	UNH iWARP interop tests group 8	Verify that iWARP parameter negotiation work.

Table 13 - Fibre Channel Gateway - (IB Specific)

Test #	Test	Description Overview
1	Basic Setup	Connect the HCA of the IB host to the IB fabric. Connect the FC Gateway to the IB Fabric. Connect the FC Gateway to the FC network or FC device. Start the SM to be used in this test.
2	Configure Gateway	Configure the FC Gateway appropriately (how to do this is vendor specific).
3	Add Storage Device	Use ibsrpdm tool in order to have the host "see" the FC storage device. Add the storage device as target.
4	Basic dd application	Run basic dd application from SRP host connected to target.
5	IB SM kill	Kill the IB master SM while test is running and check that it completes properly.
6	Disconnect Host/Target	Unload the SRP host / SRP Target (target first/host first) and check that the SRP connection is properly disconnected.
7	Load Host/Target	Load the SRP host / SRP Target. Using ibsrpdm, add the target.
8	dd after SRP Host and Target reloaded	Run basic dd application from the SRP host to the FC storage device.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

Table 13 - Fibre Channel Gateway - (IB Specific)

Test #	Test	Description Overview
9	Reboot Gateway	Reboot the FC Gateway. After FC Gateway comes up, verify using ibsrpdm tool that the host see the FC storage device. Add the storage device as target.
10	dd after FC Gateway reboot	Verify basic dd works after rebooting Gateway.

Table 14 - Ethernet Gateway - (IB Specific)

Test #	Test	Description Overview
1	Basic Setup	Connect the HCA of the IB host and Ethernet Gateway to the IB fabric. Connect the Ethernet gateway to the Ethernet network or Ethernet device. Start the SM to be used in this test.
2	Start ULP	Determine which ULP your ethernet gateway uses and be sure that ULP is running on the host.
3	Discover Gateway	Restart the ULP or using the tool provided by the ULP, make sure that the host “discovers” the Ethernet Gateway.
4	SM Failover	While the ping is running, kill the master SM. Verify that the ping data transfer is unaffected.
5	Ethernet gateway reboot	Reboot the Ethernet Gateway. After the Ethernet Gateway comes up, verify that the host can discover the Ethernet Gateway as it did before and we are able to configure the interfaces.
6	ULP restart	Restart the ULP used by Ethernet Gateway and verify that after the ULP comes up, the host can discover the Ethernet Gateway and we are able to configure the interfaces.
7	Unload/load ULP	Unload the ULP used by Ethernet Gateway and check that the Ethernet Gateway shows it disconnected. Load the ULP and verify that the Ethernet gateway shows the connection.

1.4 SUBJECTS NOT COVERED

Table 15 - Subjects Not Covered

Number	Subject/ Feature	Reason	Executor	Due Date
1	NFS-RDMA	Future Testing		October 2007
2	IPOIB connected mode	Future Testing		October 2007
3	RDS	Future Testing		October 2007
4	OpenMPI	Future Testing		October 2007

1.5 TEST REQUIREMENTS FOR OFA-UNH-IOL_LOGO_PROGRAM

The following table indicates the mandatory tests to qualify for the OFA-UNH-IOL_Logo_Program during the April 2007 Interoperability Event. It is anticipated that the Beta tests will be moved to Mandatory status for the following Interop Event.

Table 16 - Test Status for April 2007 Interop Event

Test Procedure	<i>InfiniBand Devices</i>	<i>iWARP Devices</i>	<i>Transport Independent</i>
IB Link Initialize	Mandatory	Not Applicable	
IB Fabric Initialization	Mandatory	Not Applicable	
IB IPoIB	Mandatory	Not Applicable	
TI iSER			Beta
IB SRP	Mandatory	Not Applicable	
TI SDP	Mandatory	Beta	
IB SM Failover/Handover	Beta	Not Applicable	
TI MPI - OSU			Beta
TI MPI Intel			Beta
TI uDAPL			Beta
IWARP Connectivity	Not Applicable	Mandatory	
Fibre Channel Gateway (IB)	Beta	Not Applicable	
Ethernet Gateway (IB)	Beta	Not Applicable	

1.6 TEST GLOSSARY

Table 17 Test Glossary

Technical Terms	
HCA	IB Host Channel Adapter.
TD	Test Descriptions.
SM	IB Subnet Manager.
RDF	Readme File.
SA	IB Subnet Administration.
TI	Transport Independent (tests).
RNIC	RDMA NIC (iWARP Network Interface Card).

2 GENERAL SYSTEM SETUP

Configuration

The test environment for the user interface contains:

2.1 IB HW UNITS

Table 18 IB Equipment

Equipment	Amount	Details	Check
Operating System	6 or more	The OS should be supported by OpenFabrics.	
4X IB Cables	10 or more	Between 1M => 5M.	
IB Switch from a 3rd Party Vendor	6	The number and types of switches needed from OEM is dependent on variations in embedded and subnet management and other IBTA defined management software. For example is the software on Switch A is different from the software used in Switch B, both Switches will be needed. Note that it is not dependent on number of ports supported by a switch.	
InfiniBand 4X Analyzer	1		
IB HCAs	6 or more		

2.2 IB SOFTWARE

2.2.1 LINUX/WINDOWS PLATFORMS

2.2.2 OFED - MOST CURRENT TESTED RELEASE

2.2.3 IB HCA FW – VERSION XXX - VENDOR SPECIFIC

2.2.4 IB SWITCH FW CANDIDATE – VERSION XXX - VENDOR SPECIFIC

2.2.5 IB SWITCH SW – VERSION XXX - VENDOR SPECIFIC

2.3 iWARP HW UNITS

Table 19 iWARP Equipment

Equipment	Amount	Details	Check
Operating System	4 or more	The OS should be supported by OpenFabrics.	
10GbE Cables	10		
10GbE Switch from a 3rd Party Vendor	1		
10GbE Analyzer	1		
RNICs	4 or more		

2.4 iWARP SOFTWARE

2.4.1 LINUX/WINDOWS PLATFORMS

2.4.2 OFED - MOST CURRENT TESTED RELEASE

2.4.3 iWARP RNIC FW – VERSION XXX - VENDOR SPECIFIC

2.4.4 10GBE SWITCH FW CANDIDATE – VERSION XXX - VENDOR SPECIFIC

2.4.5 10GBE SWITCH SW – VERSION XXX - VENDOR SPECIFIC

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

3 USE OF OPENFABRICS SOFTWARE FOR PRE-TESTING

Depending on the schedule of testing and bugs or issues encountered, different snapshots of latest OpenFabrics software will be used during pre-testing prior to the Interoperability Event. Any changes that result in the OpenFabrics software from interoperability testing per this test plan will be deposited back into the OpenFabrics repository so that the OpenFabrics development community will have full access to any bug fixes or feature additions that may result out of this testing effort. The frequency of such deposits will be determined based on completion of adequate testing of the said fixes or feature additions.

4 USE OF OPENFABRICS SOFTWARE FOR IBTA/CIWG INTEROPERABILITY PLUGFEST

During the pre-testing phase, UNH-IOL will apply all reasonable effort to ensure that the OpenFabrics source and binary repositories are up-to-date with the results of interoperability testing prior to IBTA/CIWG sponsored interoperability plugfest events. This will enable interoperability testing at plugfests to be conducted using software directly sourced from the OpenFabrics tree.

Should there be any issues with the OpenFabrics community not accepting certain bug fixes or features with the time frames matching with plugfest occurrences, UNH-IOL will inform all participants about the same and offer those bug fixes or features in source code and binary formats directly to the plug fest participants and InfiniBand solution suppliers.

5 USE OF OPENFABRICS SOFTWARE FOR UNH IOL iWARP INTEROPERABILITY PLUGFESTS

During the pre-testing phase, UNH IOL will apply all reasonable effort to ensure that the OpenFabrics source and binary repositories are up-to-date with the results of interoperability testing prior to UNH IOL iWARP sponsored interoperability plug fest events. This will enable interoperability testing at plug fests to be conducted using software directly sourced from the OpenFabrics tree.

Should there be any issues with the OpenFabrics community not accepting certain bug fixes or features with the time frames matching with plug fest occurrences, UNH IOL will inform all participants about the same and offer those bug fixes or features in source code and binary formats directly to the plug fest participants and iWARP solution suppliers.

6 IB HW DESCRIPTION & CONNECTIVITY

The Test contains 2 major parts - this description is for each of those parts.

6.1 BASIC CONNECTIVITY (P1P1)

6.1.1 HCA 1 SHOULD BE CONNECTED FROM PORT 1 TO LOWEST PORT NUMBER IN SWITCH

6.1.2 HCA 2 SHOULD BE CONNECTED FROM PORT 1 TO HIGHEST PORT NUMBER IN SWITCH

6.1.3 BOTH WITH 4X CABLES

6.2 SWITCHES AND SOFTWARE NEEDED

6.2.1 SWITCHES PROVIDED BY OEMS

It is necessary that Switches provided by OEMs cover the full breadth of software versions supported by the Switch OEMs. Port count is not critical for the tests. It is recommended that OEMs provide six switches covering all variations of software supported on the Switches.


6.2.2 OPENFABRICS SOFTWARE RUNNING ON HOSTS

Where there are dependencies of OEM provided and IBTA defined management software (such as subnet managers and agents, performance managers and agents etc.) with OpenFabrics software running on Hosts, such software should be provided to UNH-IOL for interoperability testing. Any known dependencies should be communicated to UNH-IOL.

6.3 CLUSTER CONNECTIVITY

6.3.1 HOSTS AND TARGETS 1-6 SHOULD BE CONNECTED FROM PORT 1 OR 2 TO PORTS X IN ALL SWITCHES USING 4X 2M CABLES.

Figure 1 Example Interop Setup



7 IWARP HW DESCRIPTION & CONNECTIVITY

The Test contains 2 major parts - this description is for each of those parts.

7.1 IWARP BASIC CONNECTIVITY (P1P1)

7.1.1 RNIC 1 ON ONE HOST SHOULD BE DIRECTLY CONNECTED TO RNIC 2 ON ANOTHER HOST

7.1.2 WITH 10GbE CABLES

7.2 SWITCHES AND SOFTWARE NEEDED

7.2.1 SWITCHES PROVIDED BY OEMS


It is necessary that Switches provided by OEMs cover the full breadth of software versions supported by the Switch OEMs. Port count is not critical for the tests. It is recommended that OEMs provide a switch per variations of software supported on the Switch.

7.2.2 OPENFABRICS SOFTWARE RUNNING ON RNICs

Where there are dependencies of OEM provided with OpenFabrics software running on RNICs, such software should be provided to UNH-IOL for interoperability testing, and any known dependencies should be communicated to UNH-IOL.

7.3 CLUSTER CONNECTIVITY

7.3.1 HOSTS AND TARGETS 1-4 SHOULD BE CONNECTED TO SWITCHES USING 10GbE CABLES.



7.4 GATEWAY, BRIDGES, ROUTERS CONNECTIVITY

TBD

8 SW & HW INSTALLATION

8.1 BURNING THE FW

8.1.1 PLEASE REFER TO FIRMWARE BURNING TOOLS AND PROCEDURES DOCUMENTATION FROM HCA IB VENDOR

8.1.2 NO FIRMWARE BURNING REQUIRED FOR IWARP VENDOR

8.2 SW INSTALLATION

8.2.1 PLEASE REFER TO SOFTWARE INSTALLATION MANUAL FROM HCA IB VENDOR.

8.2.2 PLEASE REFER TO SOFTWARE INSTALLATION MANUAL FROM RNIC VENDOR.

9 GENERAL INSTRUCTIONS

9.1 FIRST STEP INSTRUCTIONS

- 1) Burn the FW release XXX on all HCAs and RNICs using the above procedure as required by vendor.
- 2) Host and Target Configuration
 - a) Install OFED software on host systems (using a 64 bit OS) configured to run OFED.
 - b) Configure non-OFED systems for use in the cluster as per the vendors instructions.
 - c) Configure iSER/SRP targets for use in the cluster as per the vendors instructions.
- 3) Install the switch or gateway with the candidate SW stack as required by vendor.
- 4) Burn the switch or gateway with the released FW as required by vendor.
- 5) Connect the Hosts and Targets to an appropriate switch following the basic connectivity.

10 INTEROP PROCEDURES

10.1 IB LINK INITIALIZE

10.1.1 Connect the 6 HCAs (Port 1) to the switches as shown in the Cluster Connectivity Section. Cable length should be a maximum of 17 meter for SDR and 10 meters for DDR.

- 1) It is suggested that all switches be connected to one power strip to make rebooting easier.
- 2) Switches should also be located in between the servers.

10.1.2 Turn off the SM on all devices.

10.1.3 Check that all relevant green LEDs are on (Not blinking) for all HCAs and switches. All vendors should check that the link state is up and the port width is 4X.

10.1.4 Repeat Section 10.1.3 and verify that each HCA is able to link to the other HCAs in the fabric and also to all switches.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

10.2 IB FABRIC INITIALIZATION

10.2.1 Architect the Network we want to build.

- 1) Create a table of IP addresses to assign.
- 2) Create topology file - this makes sure that the subnet is configured as expected - i.e. SDR and DDR links. This inserts name of devices as well as the GUID.
- 3) See [Figure 2- Sample Network Configuration](#) below.

10.2.2 Connect the HCAs and switches as per the Architected Network and make sure that no SM/SA is running on the Fabric.

10.2.3 Run the SM/SA on one of the devices to perform device discovery, then drive all the ports through Armed and Active states.

- 1) The protocol analyzer can be used to verify SMP transaction between ports as well as to verify final port states:
 - a) For Channel Adapters, check that PortInfo:PortState=Active.
 - b) For Switches check that either PortInfo:PortState=Armed or PortInfo:PortState=Active.
- 2) ibdiagnet can be used when running openSM on an HCA.
 - a) Clear counters - ibdiagnet -pc.
 - b) Send 100 Node Descriptions - ibdiagnet -c 1000.

10.2.4 Verification Procedures

- 1) Port error counters (in PMA PortCounters) are validated to ensure that there are no ongoing link errors. The Specification says there should be no errors in 17 seconds.
- 2) There should be no bad port counters - must be zero.
- 3) No duplicate GUIDs.
- 4) SM verification
 - a) Verify that the SM running is the one you specified. Check /tmp/ibdiagnet.sm.
 - b) Verify number of nodes and switches in the network.


Restart all devices in the fabric and follow Sections 10.2.3 through 10.2.4 and each time run the SM/SA from a different component in the system switch/HCA.

Table 20 - ibdiagnet commands

Commands	Description
ibdiagnet -h	Help
ibdiagnet - pc	Clear Counter
ibdiagnet -lw 4x - ls 2.5	Specify link width and speed
ibdiagnet -c 1000	send 1000 Node Descriptions

Figure 2 - Sample Network Configuration

1
 2



38
 39
 40
 41
 42

10.3 IB IPoIB

10.3.1 Setup

This procedure, as the previous ones, will be based on the cluster connectivity. An SM/SA which supports IPoIB (sufficient IB multicast support) will be running on the HCAs, or if a corresponding connected HCA does not support this capability, it can run on a switch with an embedded SM/SA or a third HCA which would only run SM/SA for the partner pair (with a switch in the middle).

In the procedures below, an IB analyzer is inserted in the appropriate link to obtain traces and validate the aspects of the procedures specifically detailed below in subsequent sections.

10.3.2 IPoIB Interface Creation and IPoIB Subnet Creation

A single IPoIB subnet is reserved for Plugfest IPoIB testing. This subnet to be setup on the full default partition (0xFFFF). Its IPoIB address is 10.0.0.x/8 (10.0.0.x/netmask 255.255.255.0).

Once the IPoIB interfaces are configured on all partner HCA ports, the following procedures will be performed. The default IPoIB MTU of 2048 will be used.

The ability for each partner to create the all-IPoIB nodes IB multicast group, if observable, as well as to join that multicast group is tested.

In some configurations, when the SM/SA is local to the IPoIB implementation, not all operations will be observable with the IB analyzer (when the side with the SM/SA creates the IPoIB broadcast group). Additionally, with some SM/SAs, the creation of the IPoIB broadcast group may be previously administered and hence would not be observable by an IB analyzer.

In addition, the procedure will test the SM/SA ability to support the following functions:

- 1) SA in terms of performing the multicast group creation and joining.
- 2) SM in terms of programming the multicast topology (MulticastForwarding-Table) in any switches.

The various parameters of the MCMemberRecord will be validated. In general, it will be checked that the group creator characteristics (Q_Key, etc.) are returned to the subsequent group joiners.

10.3.3 Ping Procedures

Step A

- 1) Assign IP Addresses using the command `ifconfig ib0 10.0.0.x netmask 255.255.0.0`
- 2) Turn off SMs. Use `ibdiagnet` to verify that the master SM is missing.
- 3) Power cycle all switches.
 - a) This insures that the new SM will configure all the links and create the multi-cast join.

- b) Run ibdiagnet to verify that all nodes have come up. Ibdagnet does not require the SM to discover the node. 1
- 4) Use ibdiagnet to determine that all nodes and switches were discovered. 2
- Note:** Ibdagnet may show more switches than indicated by the physical number of switch platforms present. This is because some switches have multiple switch chips. 3
- 5) Run SM/SA from one of the nodes in the cluster. 4
- a) Verify that the new SM is the master. You will need to know the GUID of the device since the SM will be reassigned on each reboot. 5
- 6) Pings (ICMP requests) of the following lengths will be performed from each node (All to all): first in one direction, then the other, and finally bidirectional: 64, 256, 511, 512, 1024, 1025, 2044, 4096, 8192, 16384, 32768 and 65507. The count is 100. 6
- Note:** In the above, the lengths of the IP (20 bytes for IPoIB Encapsulation) and IB headers are included although they will need to be subtracted out on the actual invocation of the ping command. It is also unknown whether the standard ping application without modification will allow all the lengths specified above. 7
- An IB trace of this should be examined to make sure that: 8
- 1) ARP is resolved properly (both ARP request and response are properly formatted). 9
- 2) Proper fragmentation (at the IB level) is occurring. 10
- Note:** the case of length of 65536 ("ping of death" or long ICMP) exceeds the maximum IP length and no response is expected for this case. 11
- Note:** At the completion of each different ping invocation, the arp table should be locally examined (via arp -a) and then the partner should be removed from the arp table (via arp -d) prior to starting the next ping invocation. 12
- Step B** 13
- 1) Bring up all HCAs but one. 14
- 2) Check for ping response between all players. 15
- 3) Disconnect one more HCA from the cluster (you should see that the ping stopped). 16
- 4) Ping to the newly disconnected HCA from all nodes (No response should be returned). 17
- 5) Connect the first machine (the one that was not connected) and check for ping response. 18
- 6) Connect the disconnected HCA to a different switch on the subnet which will change the topology. Check for ping response. 19
- 7) Ping again from all nodes (this time we should get a response). 20
- 8) Follow steps 1 to 7, this time bring the interface down and then back up using ifconfig ibX down and ifconfig ibX up commands. 21
- Step C** 22
- Follow Step A and B running the SM/SA from each device in the cluster (If all HCAs have the same SW no need to test more than one HCA/node). 23

10.3.4 FTP PROCEDURE

FTP procedures require an FTP server to be configured on each machine in the partner pair.

An FTP client needs to be available on each machine as well.

A 4 MB file will be FTP'd to the partner and then FTP'd back and binary compared to the original file, this will be done in each direction and then bidirectional.

Step A

- 1) Make sure vsftpd is installed on each node for FTP application.
- 2) A special account for this should be created as follows:
 - b) Username: Interop
 - c) Password: openfabrics

Step B

Run FTP server on all nodes.

- 1) For each node:
 - a) Connect via FTP on IPoIB using the specified user name and passwd.
 - b) Put the 4MB file to the /tmp dir on the remote host * 4 times.
 - c) Get the same file to your local dir again 4 * times.
 - d) Compare the file using the command *cmp tfile tfile.orig*.

10.4 TI iSER

10.4.1 IB Setup

Connect initiator/target to switch as well as run one or more SMs (embedded in the switch or host based). If more than one SM, let the SMs split into master and slave. In the procedures below, an IB analyzer is inserted in the appropriate link to obtain traces and validate the aspects of the procedures specifically detailed below in subsequent sections.

10.4.2 iWARP Setup

Connect iSER host initiator and target RNICs to an 10GbE switch.

10.4.3 Procedure

- 1) Load iSER target and iSER initiator to hosts from OpenFabrics tree, check iSER connection.
- 2) Run basic dd application from iSER initiator host connected to target.
- 3) [IB Specific Test] Run basic dd application from iSER initiator host connected to target. Kill the master SM while test is running and check that it completes properly.
- 4) Unload iSER initiator from a Host and check iSER connection properly disconnected on a target host.
- 5) Unload iSER target from a Host and check iSER connection properly disconnected on an initiator host.
- 6) [IB Specific Test] Repeat steps 2-5 now with the previous slave SM (we did not actually stop the target).

10.5 IB SRP

Step A

Connect 2 HCAs to one of the switches and if possible, run SM/SA from the switch. If not, then run the SM/SA from one of the HCAs.

1) Initial Setup

- a) Run *ibnetdiscover* - this will show the devices that are connected on the network.
- b) Verify that you have an SM running.
- c) Run *modprobe ib-srp* - this will insert the module for SRP.
- d) Run *lsmod | grep ib_srp* - this will verify that the module has loaded.

2) Load SRP target and then Host, check SRP connection.

3) Load SRP host then target, and check the rescan utility.

4) Run basic dd application from SRP host connected to target.

5) Run basic dd application from SRP host connected to target. Kill the master SM while test is running and check that it completes properly.

6) Unload SRP Host / SRP target (target first / host first) and check SRP connection properly disconnected.

Follow those steps with all switches available.

1) Run SM/SA from every node/switch.

2) SM/SA can be running from all nodes.

Step B

Disconnect one of the Hosts from the switch and reconnect, then run basic dd application both from host and target.

10.6 TI SDP

10.6.1 IB SETUP

This procedure, as the previous ones, will be based on the cluster connectivity. An SM/SA which supports IPoIB (sufficient IB multicast support) will be running on the HCAs, or on a switch with an embedded SM/SA or a third HCA which would only run SM/SA for the partner pair (with a switch in the middle). This procedure has been developed for Linux and maybe ported to Windows if there is sufficient vendor support.

In the procedures below, an IB analyzer is inserted in the appropriate link to obtain traces and validate the aspects of the procedures specifically detailed below in subsequent sections.

10.6.2 IWARP SETUP

Connect SDP host client and server RNICs to an 10GbE switch.

10.6.3 INSTALLATION REQUIREMENTS

Make sure the following are installed on all nodes:

- 1) vsftpd - for FTP application.
- 2) sshd - for SCP application.

10.6.4 CREATING A USER NAME

Special account for this should be created as follows:

- 1) Username: interop.
- 2) Password: openfabrics.

10.6.5 ENVIRONMENT VARIABLES

- 1) Set LD_PRELOAD to:
 - a) On 64bit machines - /DEFAULT_INSTALL_LOCATION/lib64/libsdp.so
 - b) On 32bit machines - /DEFAULT_INSTALL_LOCATION /lib/libsdp.so
 - c) **Example:** export LD_Preload=/usr/local//lib64/libsdp.so
- 2) Set SIMPLE_LIBSDP to 1 - this says to use SDP
 - a) **Example:** export SIMPLE_LIBSDP=1
- 3) After setting the environment variables restart the xinetd.
 - a) **Example:** /etc/init.d/xinetd restart

10.6.6 NETPERF PROCEDURE

Step A

Each node will act as server.

- 1) For each node:
 - a) Run. /netserver -p {port number}
- 2) From all the other nodes run:

- a) [For IB] . /net perf -p {port number} -H {server nod's IPoIB} -l 1 -t TCP_STREAM -- -m {message size} -s {local buffer size}
- a) [For iWARP] . /net perf -p {port number} -H {server nod's IP} -l 1 -t TCP_STREAM -- -m {message size} -s {local buffer size}
- b) i.e. /net perf -p 2006 -H 11.4.10.36 -l 1 -t TCP_STREAM -- -m 1000 -s 1024
- c) Where message size is 10, 100, 1000, 10000 and local buffer size is 1024, 6000.

- 3) Tests are expected to end on all nodes.
- 4) A zip file with all src files will be added.

Step B

Kill the server running on each node.

10.6.7 FTP PROCEDURE

FTP procedures require an FTP server to be configured on each machine in the partner pair.

An FTP client needs to be available on each machine as well.

A 4 MB file will be FTP'd to the partner and then FTP'd back and binary compared to the original file, this will be done in each direction and then bidirectional.

Step A

Setup

- 1) Open one window to each of the partners being tested.
- 2) Export the environment variable on each partner.
- 3) Create user name and password as specified in 10.6.4.
- 4) Start the FTP Daemon on both partners.
 - a) **Example:** /etc/init.d/ftpd start
- 5) Verify SDP is running.
 - a) Ismod | grep sdp
 - a) ib_sdp should be greater than 0 - reference count should be greater than 0. Each connection opens three reference counts.

Procedure

- 1) For each node:
 - a) Connect via FTP on IPoIB using the specified user name and passwd.
 - b) Put the 4MB file to the /tmp dir on the remote host * 4 times.
 - c) Get the same file to your local dir again 4 * times.
 - d) Compare the file.
- 2) During this transaction double check that sdp connection has been established, you can see it in /proc/net/sdp/conn_main.

10.6.8 SCP PROCEDURE

- 1) For each node:
 - a) [For IB] Connect via SCP on IPoIB address from all other nodes uploading and downloading a file.
 - a) [For iWARP] Connect via SCP from all other nodes uploading and downloading a file.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

10.7 IB SM FAILOVER AND HANDOVER PROCEDURE

10.7.1 SETUP

- 1) Connect 2 HCAs to one of the switches.
- 2) In this test, all active SMs on the fabric which are going to be tested, must be from the same vendor.

10.7.2 PROCEDURE

Make sure the following are installed on all nodes:

- 1) Disable all SMs on the cluster until only one SM is still active.
- 2) Using the Agilent Exerciser, verify that all SMs are NOT ACTIVE (after receiving the SMSet of SMInfo to DISABLE) and that the selected SM (SM1) is the master (query PortInfo:SMLid should show the selected SM as active).
- 3) Start another SM (SM2) on the Subnet.
- 4) Verify Subnet and SMs behavior according to the SMs priority.
- 5) If SM1 priority is higher then the new SM2 priority then:
 - a) Verify new SM2 goes into STANDBY and the MASTER SM1 is still the same one.
- 6) Disable MASTER SM1.
- 7) Verify the new active SM (SM2) goes into MASTER SM state and cluster nodes are configured accordingly.
- 8) Re-enable the original SM (SM1).
- 9) Next, verify SM1 goes into MASTER SM state and cluster nodes are configured accordingly while SM2 goes into STANDBY state.
- 10) Disable SM1.
- 11) Verify SM2 goes into MASTER SM state and cluster nodes are configured accordingly.
- 12) The utility osmttest should be used to validate the SA after failover/handover
- 13) Repeat steps 3 through 12 till all SMs, which are from the same vendor and are active on the subnet, have participated in the test.

Follow these steps with all switches available.

10.8 TI MPI - OHIO STATE UNIVERSITY

10.8.1 SETUP

- 1) Download and install MPI from:
<http://nowlab.cse.ohio-state.edu/projects/mpi-iba>
- 2) Download and install Intel® MPI Benchmarks from:
<http://www.intel.com/cd/software/products/asm-na/eng/308295.htm>
- 3) Software package should be installed on all cluster nodes with typical configuration. The IMB tests must be compiled with the -DCHECK compiler flag set, to enable automatic self-checking of the results.
- 4) All cluster nodes should be connected and SM should be running from one management node.

10.8.2 TEST PROCEDURE

Step A:

Enter the management node and define the following params:

- 1) \$MPIHOME - path to mpi home directory.
- 2) \$NP - number of jobs that you want run in the system (usual it is equal to [number of CPUs per node] X [number of nodes]).
- 3) \$HOSTFILE - path to host file with list of all nodes in the system.
- 4) \$PMB_HOME - path to Intel® MPI Benchmarks location.

Step B

Run Intel® MPI Benchmarks:

- 1) Two sets of tests should be run, with these command lines
 - a) \$MPIHOME/bin/mpirun_rsh -np \$NP -hostfile \$HOSTFILE \$PMB_HOME/PMB-MPI1 -multi 0 PingPong PingPing
 - a) \$MPIHOME/bin/mpirun_rsh -np \$NP -hostfile \$HOSTFILE \$PMB_HOME/PMB-MPI1

The first command runs just the PingPong and PingPing point-to-point tests, but makes all tasks active (pairwise).

The second command runs all the tests (PingPong, PingPing, Sendrecv, Exchange, Bcast, Allgather, Allgatherv, Alltoall, Reduce, Reduce_scatter, Allreduce, Barrier), in non-multi mode.
- 2) If the test passes move to the next SM in the cluster, and run the test again.

10.9 MPI - INTEL MPI - (NOT PART OF THE OFA STACK)

10.9.1 GENERAL ISSUES

- 1) Network configuration requirements
 - a) Ethernet must be installed and configured on all systems.
 - b) DNS names must match hostnames.
 - c) /etc/hosts should be setup with static IB hostnames and addresses.
- 2) OFED Installation requirements
 - a) OFED library path must be configured on all systems (ldconfig should be executed after OFED installation).
 - b) OFED uDAPL /etc/dat.conf must match /sbin/ifconfig setup.
- 3) Setup Requirements
 - a) All systems must be setup with identical user accounts on all nodes (SSH access with no password prompts (key's setup) or rsh with .rhosts setup).
 - b) Requires NFS setup from headnode and mount points (/home/test/export) on user accounts.

Note: any node on the cluster can be setup as the headnode.
 - c) MPI testing requires a reliable IB fabric without other fabric interop testing occurring.
- 4) Here is the location for the free Intel MPI runtime environment kit
 - a) <http://www.intel.com/cd/software/products/asmo-na/eng/222346.htm>
- 5) Here is the location for the Intel MPI Benchmarks
 - a) <http://www.intel.com/cd/software/products/asmo-na/eng/cluster/mpi/219848.htm>

10.9.2 SETUP FOR THE CLUSTER

- 1) Install same O/S version on homogenous x86_64 systems. (Recommend RH EL4 U4, EM64T)
- 2) Install Ethernet interface with dynamic addresses from DHCP and hostnames registered with DNS.
- 3) Verify "hostname" on each system returns the hostname that DNS reports.

10.9.3 Setup information for OFED

- 1) Install OFED 1.2 on all systems.
- 2) Bump up the max locked memory limits on the system.
edit /etc/security/limits.conf and add the following:
* hard memlock 500000
* soft memlock 500000
- 3) Run /sbin/ldconfig to pick up new OFED library path
- 4) Modify /etc/hosts and add IB hostnames and addresses for the IB network interfaces

- 5) Modify /etc/dat.conf and change the netdev reference to the appropriate interface (ib0 or ib1) being used
- 6) Run OpenSM either on the headnode OR from one of the switches. Verify by pinging IB addresses on all systems.

10.9.4 Setup information for Intel MPI

- 1) Install Intel MPI in /opt/intel/mpi/3.0 on every system.
- 2) Add identical user account (/home/test) on every system. For example
"useradd -m test -u 555 -g users"
- 3) Update the .bashrc for /home/test on every system:
export PATH=\$PATH:./
source /opt/intel/mpi/3.0/bin64/mpivars.sh
for IB, (mpi will default to rdssm if nothing defined)
export I_MPI_DEVICE=rdssm
for ethernet
export I_MPI_DEVICE=sock
export MPIEXEC_TIMEOUT=180
ulimit -c unlimited
- 4) Add .mpd.conf file in /home/test on every system.
add single line "MPD_SECRETWORD=testing" to .mpd.conf
chmod 600 /home/test/.mpd.conf
- 5) Add 2 mpd.hosts files in /home/test on the headnode, one for ethernet and one for IB
Create mpd.hosts.ethernet and add a line for every system on the cluster using ethernet addresses or hostnames
Create mpd.hosts.ib and add a line for every system on the cluster using IPoIB addresses
- 6) Add nfs export /home/test/export on headnode and change /etc/fstab for mount points:
edit /etc/exports and add "/home/test/exports *(rw)" on headnode
edit /etc/fstab and add "hostname:/home/test/exports /home/test/exports nfs" on all other nodes
- 7) Untar the Intel Test Suites on the headnode in /home/test/exports
- 8) run mpdboot on the head node. For example: if you have 6 nodes on the cluster and want to run over ethernet:
From the /home/test directory run: "mpdboot -n 6 -r ssh -f ./mpd.host.ethernet"
- 9) Run test suite over Ethernet to validate your installation:

“export I_MPI_DEVICE = sock”

run tests...(refer to test plan)

“mpdallexit”

10) Run test suite over IB

export I_MPI_DEVICE = rdssm

mpdboot -n 6 -r ssh -f ./mpd.host.ib

run tests.... (refer to test plan)

“mpdallexit”

10.9.5 ADDITIONAL INFORMATION

- 1) Go to the individual test directories and follow the steps in the respective README-*.txt files. The recommended order for running the test suites in the order of increasing execution time:

a) mpich2-test: see README-mpich2-test.txt file.

- 2) For Intel MPI Support Services go to:

<http://www.intel.com/support/performance/tools/cluster/mapi/index.htm>

See the Intel MPI Reference Manual for Additional information

10.9.6 INTEL MPI BENCHMARK SETUP

The IMB tests must be compiled with the -DCHECK compiler flag set, to enable automatic self-checking of the results. Modify the appropriate make_arch file as follow:

MPI_HOME =

MPI_INCLUDE = .

LIB_PATH =

LIBS =

CC = mpicc

OPTFLAGS = -O

CLINKER = \${CC}

LDFLAGS =

CPPFLAGS =

10.9.7 INTEL IHV TEST SUITE SETUP

All test suites are configured, built, and run in a uniform way.

- Configure for mpich-test ./configure --with-mpich2=/opt/intel/mapi/3.0
- Configure for mpich2-test: ./configure --with-mpich2=/opt/intel/mapi/3.0 --cc=mpicc -f77=mpif77 -cxx=mpicxx
- Configure for IntelMPITEST: ./configure --with-mpich2=/opt/intel/mapi/3.0

- 1) If you installed the library to another location, then replace the default Intel(R) MPI Library installation path "/opt/intel/mpi/2.0".

A detailed description of the extra configuration options is contained in the respective README-*.txt file.

- 2) Run the tests:

If you use a Bourne-compatible shell (sh, bash, ksh, etc.), do:

```
export MPIEXEC_TIMEOUT=180
```

```
nohup make testing > xlog 2>&1 &
```

If you use a Csh-compatible shell (csh, tcsh, etc.), do:

```
setenv MPIEXEC_TIMEOUT 180
```

```
nohup make testing >&! xlog &
```

The expected duration of the test run is detailed in the respective README-*.txt file.

- 3) Check the results:

```
grep ">pass" summary.xml | wc -l
```

```
grep ">fail" summary.xml | wc -l
```

The exact number of passed and failed tests is specified in the respective README-*.txt file.

10.9.8 TEST PROCEDURE

These sets of tests should be run for both Intel mpich2-test and the IntelIMPITEST suite:

Note: "Set ulimit -c unlimited" to capture core files in case of abnormal terminations.

Test suite mpich2-test: use default settings with no environment variables.

Test suite IntelIMPITEST: use default settings with no environment variables.

10.9.9 INTERPRETING THE RESULTS

- 1) For mpich2-test test suites:

The **summary.xml** file produced by the test suites has the following uniform format:

- The file header contains information on the test suite and testing environment.
- The rest of the file represents the results of the test suite run.

- 2) For IntelIMPITEST test suite:

The **Tests/summary.xml** file produced by the test suites has the following uniform format:

- The file header contains information on the test suite and testing environment

- The rest of the file represents the results of the test suite run.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

10.10 TI uDAPLTEST COMMANDS

Server Command: daplttest -T S -D <ia_name>

10.10.1 GROUP 1: POINT-TO-POINT TOPOLOGY

[1.1] 1 connection and simple send/recv:

- daplttest -T T -s <server_name> -D <ia_name> -i 100 -t 1 -w 1 -R BE
- client SR 256 1 server SR 256 1

[1.2] Verification, polling, and scatter gather list:

- daplttest -T T -s <server_name> -D <ia_name> -i 100 -t 1 -w 1 -V -P -R BE
- client SR 1024 3 -f \
- server SR 1536 2 -f

10.10.2 GROUP 2: SWITCHED TOPOLOGY

InfiniBand Switch: Any InfiniBand switch

iWARP Switch: 10 GbE Switch

[2.1] Verification and private data:

- daplttest -T T -s <server_name> -D <ia_name> -i 100 -t 1 -w 1 -V -P -R BE
- client SR 1024 1 \
- server SR 1024 1

[2.2] Add multiple endpoints, polling, and scatter gather list:

- daplttest -T T -s <server_name> -D <ia_name> -i 100 -t 1 -w 10 -V -P -R
- BE client SR 1024 3 \
- server SR 1536 2

[2.3] Add RDMA Write :

- daplttest -T T -s <server_name> -D <ia_name> -i 100 -t 1 -w 1 -V -P -R BE
- client SR 256 1 \
- server RW 4096 1 server SR 256 1

[2.4] Add RDMA Read:

- daplttest -T T -s <server_name> -D <ia_name> -i 100 -t 1 -w 1 -V -P -R BE
- client SR 256 1 \
- server RR 4096 1 server SR 256 1

10.10.3 GROUP 3: SWITCHED TOPOLOGY WITH MULTIPLE SWITCHES

[3.1] Multiple threads, RDMA Read, and RDMA Write:

- daplttest -T T -s <server_name> -D <ia_name> -i 100 -t 4 -w 8 -V -P -R BE
- client SR 256 1 \
- server RR 4096 1 server SR 256 1 client SR 256 1 server RR 4096 1 \
- server SR 256 1

[3.2] Pipeline test with RDMA Write and scatter gather list:

- `dapltest -T P -s <server_name> -D <ia_name> -i 1024 -p 64 -m p RW 8192 2` 1
 - [3.3] Pipeline with RDMA Read: 2
 - **InfiniBand**: `dapltest -T P -s <server_name> -D <ia_name> -i 1024 -p 64 -m p RR 4096 2` 3
 - **iWARP**: `dapltest -T P -s <server_name> -D <ia_name> -i 1024 -p 64 -m p RR 4096 1` 4
 - [3.4] Multiple switches: 5
 - `dapltest -T T -s <server_name> -D <ia_name> -i 100 -t 1 -w 10 -V -P -R` 6
 - BE client SR 1024 3 \ 7
 - server SR 1536 2 8
- 9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

10.11 iWARP CONNECTIVITY

10.11.1 UNH-IOL INTEROP SUITE

See [UNH-IOL iWARP Interoperability Test Suite](#) for full details

10.11.2 iWARP SETUP

The interoperability tests can be run in point to point mode or switched. Connect 2 iWARP hosts RNICs together or to a 10GbE switch.

10.11.3 TEST PROCEDURE

Step A:

Group 1: Single RDMA Operations Over A Single Connection:

- TEST 1.1: RDMA WRITE
- TEST 1.2: RDMA READ
- TEST 1.3: RDMA SEND
- TEST 1.4: RDMA SENDINV
- TEST 1.5: RDMA SENDSE
- TEST 1.6: RDMA SENDSEINV
- TEST 1.7: RDMA TERMINATE
- TEST 1.8: LARGE RDMA WRITE
- TEST 1.9: LARGE RDMA READ

Step B

Group 2: Multiple RDMA Operations Over A Single Connection:

- Test 2.1: Sequence of 10 RDMA Write Commands
- Test 2.2: Sequence of 10 RDMA Read Commands
- Test 2.3: Sequence of 10 RDMA Send Commands
- Test 2.4: Sequence of 10 RDMA Sendinv Commands
- Test 2.5: Sequence of 10 RDMA Sendse Commands
- Test 2.6: Sequence of 10 RDMA Sendseinv Commands
- Test 2.7: Sequence of 10 RDMA Terminate Commands
- Test 2.8: Sequence of Interleaved RDMA Write And Read Commands
- Test 2.9: Sequence of Interleaved RDMA Write And Terminate Commands
- Test 2.10: Sequence of Interleaved RDMA Read And Terminate Commands
- Test 2.11: Sequence of Interleaved RDMA Send And Terminate Commands

	• Test 2.12: Sequence of Interleaved RDMA Sendinv And Terminate Commands	1 2
	• Test 2.13: Sequence of Interleaved RDMA Sendse And Terminate Commands	3 4
	• Test 2.14: Sequence of Interleaved RDMA Sendseinv And Terminate Commands	5 6
	• Test 2.15: Sequence of Interleaved RDMA Write With All Other RDMA Commands	7 8
	• Test 2.16: Sequence of Interleaved RDMA Read With All Other RDMA Commands	9 10
	• Test 2.17: Sequence of Interleaved RDMA Send With All Other RDMA Commands	11 12
	• Test 2.18: Sequence of Interleaved RDMA Sendinv With All Other RDMA Commands	13 14
	• Test 2.19: Sequence of Interleaved RDMA Sendse With All Other RDMA Commands	15 16
	• Test 2.20: Sequence of Interleaved RDMA Sendseinv With All Other RDMA Commands	17 18 19
Step C	Group 3: Multiple Connections:	20
	• Test 3.1: Single RDMA Operations Over Multiple Connections	21 22
	• Test 3.2: Multiple RDMA Operations Over Multiple Connections	23 24
	• Test 3.3: RDMA Operations Over 25 Connections	25
	• Test 3.4: Simultaneous Operations Over 25 Connections	26 27
Step D	Group 4: Disconnect/Reconnect Physical Connections:	28
	• Test 4.1: Termination Followed By A WRITE	29 30
	• Test 4.2: Termination Followed By A READ	31 32
Step E	Group 5: Speed Negotiation:	33
	• Test 5.1: RNICs Operating At 10g And 1g Speed	34 35 36
Step F	Group 6: RDMA Error Ratio:	37
	• Test 6.1: Sequence of All Zeros	38
	• Test 6.2: Sequence of All Ones	39 40
	• Test 6.3: Sequence of Ones Followed By Zeros	41 42

	• Test 6.4: Sequence of Interleaved Ones And Zeros	1
		2
		3
Step G	Group 7: Stress Patterns Over RDMA:	4
		5
	• Test 7.1: RDMA Read After Prolonged RDMA Write Operations	6
	• Test 7.2: RDMA Read After Prolonged RDMA Read Operations	7
	• Test 7.3: RDMA Read After Prolonged RDMA Send Operations	8
	• Test 7.4: RDMA Read After Prolonged RDMA Sendinv Operations	9
	• Test 7.5: RDMA Read After Prolonged RDMA Sendse Operations	10
	• Test 7.6: RDMA Read After Prolonged RDMA Sendseinv Operations	11
		12
		13
		14
Step H	Group 8: Parameters:	15
		16
	• Test 8.1: Markers Support	17
	• Test 8.2: CRC Support	18
		19
		20
		21
		22
		23
		24
		25
		26
		27
		28
		29
		30
		31
		32
		33
		34
		35
		36
		37
		38
		39
		40
		41
		42

10.12 FIBRE CHANNEL GATEWAY

10.12.1 Procedure

- 1) Connect the HCA of the IB host to the IB fabric. Connect the FC Gateway to the IB Fabric (how to do this is determined by the FC Gateway vendor). Connect the FC Gateway to the FC network or FC device. Start the SM to be used in this test.
- 2) Configure the FC Gateway appropriately (how to do this is vendor specific).
- 3) Use ibsrpdm tool in order to have the host "see" the FC storage device. Add the storage device as target.
- 4) Run basic dd application from the SRP host to the FC storage device.
- 5) Run basic dd application from the SRP host to the FC storage device. While the test is running, kill the master SM. Verify that the test completes properly.
- 6) Unload the SRP host / SRP Target (target first/host first) and check that the SRP connection is properly disconnected.
- 7) Load the SRP host / SRP Target. Using ibsrpdm, add the target.
- 8) Run basic dd application from the SRP host to the FC storage device.
- 9) Reboot the FC Gateway. After FC Gateway comes up, verify using ibsrpdm tool that the host see the FC storage device. Add the storage device as target.
- 10) Run basic dd application from the SRP host to the FC storage device.
- 11) Follow steps 1-10 above with each SM to be tested and with each HCA to be tested, until each HCA and each SM has been tested with the FC Gateway.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

10.13 ETHERNET GATEWAY

10.13.1 Procedure

- 1) Connect the HCA of the IB host to the IB fabric. Connect the Ethernet Gateway to the IB fabric. Connect the Ethernet gateway to the Ethernet network or Ethernet device. Start the SM to be used in this test.
- 2) Determine which ULP your ethernet gateway uses and be sure that ULP is running on the host (VNIC or IPoIB).
- 3) Restart the ULP or using the tool provided by the ULP, make sure that the host "discovers" the Ethernet Gateway. Configure the interfaces and make sure they are up.
- 4) Run ping from the host to the Ethernet device. While the ping is running, kill the master SM. Verify that the ping data transfer is unaffected.
- 5) Reboot the Ethernet Gateway. After the Ethernet Gateway comes up, verify that the host can discover the Ethernet Gateway as it did before and we are able to configure the interfaces.
- 6) Restart the ULP used by Ethernet Gateway and verify that after the ULP comes up, the host can discover the Ethernet Gateway and we are able to configure the interfaces.
- 7) Unload the ULP used by Ethernet Gateway and check that the Ethernet Gateway shows it disconnected. Load the ULP and verify that the Ethernet gateway shows the connection.
- 8) Repeat step 4 by using ssh and scp instead of ping.

11 BUG REPORTING METHODOLOGY DURING PRE-TESTING

The following bug reporting methodology will be followed during the execution of interoperability pre-testing at UNH-IOL.

- 1) UNH-IOL and the OEMs (i.e., Cisco, Mellanox, QLogic, Voltaire, NetEffect and Chelsio) will assign a focal point of contact to enable fast resolution of problems.
- 2) Bug reports will include:
 - a) Detailed fail report with all relevant detail (Test/Application, Topology.).
 - b) [For IB] IB trace if needed.
 - c) [For iWARP] iWARP, TCP and SCTP traces if needed.
- 3) Bug reports will be sent via mail by UNH-IOL to the focal point assigned by the switch OEM
- 4) Bug reports and suggested fixes will be sent to the OpenFabrics development community. When such reports are communicated, UNH-IOL will ensure that confidentiality between UNH-IOL and the switch OEM will be maintained. Bug reports will be generalized and not include any company specific proprietary information such as product name, software name, version etc.
- 5) All bug fixes/issues that we will found during testing will be uploaded to the OpenFabrics repository. Documentation related to fixes will not mention any company specific proprietary information.

Note: This test plan does not cover how bugs will be reported by IBTA/CIWG or IETF iWARP during or after interoperability testing at plugfests.

12 TEST SUMMARY

Please add a check mark whenever a test case passes and when the system is behaving according to the criteria mentioned below. Otherwise indicate a failure along with a comment explaining the nature of the failure.

Table 21 - IB Link Up

Test #	Test	Pass	Fail	Comment
1	Phy link up all ports			
2	Logical link up all ports switch SM			
3	Logical link up all ports HCA SM			

Table 22 - IB Fabric Initialization

Test #	Test	Pass	Fail	Comment
1	Verify that all ports are in Armed or Active state			

Table 23 - IB IPoIB

Test #	Test	Pass	Fail	Comment
1	Ping all to all - Ping using SM 1			
2	Ping all to all - Ping using SM 2			
3	Ping all to all - Ping using SM 3			
4	Ping all to all - Ping using SM 4			
5	Ping all to all - Ping using SM 5			
6	Ping all to all - Ping using SM 6			
7	Ping all to all - Ping using SM x			
8	Connect/Disconnect Host			
9	FTP Procedure			

Table 24 - TI iSER

Test #	Test	Pass	Fail	Comment
1	Basic dd application			

Table 24 - TI iSER

Test #	Test	Pass	Fail	Comment
2	IB SM kill			
3	Disconnect Initiator			
4	Disconnect Target			
5	Repeat with previous SM Slave			

Table 25 - IB SRP

Test #	Test	Pass	Fail	Comment
1	Basic dd application			
2	IB SM kill			
3	Disconnect Initiator			
4	Disconnect Target			

Table 26 - TI SDP

Test #	Test	Pass	Fail	Comment
1	netperf procedure			
2	FTP Procedure			
3	IB SCP Procedure			
4	iWARP SCP Procedure			

Table 27 - IB SM

Test #	Test	Pass	Fail	Comment
1	Basic sweep test			
2	SM Priority test			
3	Failover test - Disable SM1			
4	Failover test - Disable SM2			

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

Table 28 TI MPI - OSU

Test #	Test	Pass	Fail	Comment
1	Test 1: PingPong			
2	Test 1: PingPing point-to-point			
3	Test 2: PingPong			
4	Test 2: PingPing			
5	Test 2: Sendrecv			
6	Test 2: Exchange			
7	Test 2: Bcast			
8	Test 2: Allgather			
9	Test 2: Allgatherv			
10	Test 2: Alltoall			
11	Test 2: Reduce			
12	Test 2: Reduce_scatter			
13	Test 2: Allreduce			
14	Test 2: Barrie			

Table 29 TI MPI Intel (Not part of OFA stack) Pass/Fail Summary

Test #	Test Suite	Pass	Fail	Comment
1	MPICH2-test			
2	IntelMPItest			

Table 30 TI MPI Intel (Not part of OFA stack) Test Failure Details

Test #	Test Suite	Test Section & Name	Comment
1			
2			
3			
4			
5			

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

Table 30 TI MPI Intel (Not part of OFA stack) Test Failure Details

Test #	Test Suite	Test Section & Name	Comment
6			
7			
8			

Table 31 -TI uDAPL

Test #	Test	Pass	Fail	Comment
1	P2P - Connection & simple send receive			
2	P2P - Verification, polling & scatter gather list			
3	Switched Topology -Verification and private data			
4	Switched Topology - Add multiple endpoints, polling, & scatter gather list			
5	Switched Topology - Add RDMA Write			
6	Switched Topology - Add RDMA Read			
7	Multiple Switches - Multiple threads, RDMA Read, & RDMA Write			
8	Multiple Switches - Pipeline test with RDMA Write & scatter gather list			
9	Multiple Switches - Pipeline with RDMA Read			
10	Multiple Switches - Multiple switches			

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

Table 32 iWARP Connectivity

Test #	Test	Pass	Fail	Comment
1	Group 1 - Verify that each single iWARP operation over single connection works			
2	Group 2 - Verify that multiple iWARP operations over a single connection work			
3	Group 3 - Verify that multiple iWARP connections work			
4	Group 4 - Verify that disconnect/reconnect physical connections work			
5	Group 5 - Verify that IP Speed negotiation work			
6	Group 6 - Verify that iWARP error ratio work			
7	Group 7 - Verify that stress pattern over iWARP work			
8	Group 8 - Verify that iWARP parameter negotiation work			

Table 33 Fibre Channel Gateway - (IB Specific)

Test #	Test	Pass	Fail	Comment
1	Basic Setup			
2	Configure Gateway			
3	Add Storage Device			
4	Basic dd application			
5	IB SM kill			
6	Disconnect Host/Target			
7	Load Host/Target			
8	dd after SRP Host and Target reloaded			
9	Reboot Gateway			
10	dd after FC Gateway reboot			

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42

Table 34 Ethernet Gateway - (IB Specific)

Test #	Test	Pass	Fail	Comment
1	Basic Setup			
2	Start ULP			
3	Discover Gateway			
4	SM Failover			
5	Ethernet gateway reboot			
6	ULP restart			
7	Unload/load ULP			

Table 35 Remarks

General Remarks: Comments about the set-up, required updates to the TD, and any other issues that came up during the testing.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42