### **Fibre Channel Consortium**

FC-BB-5 FCoE Initialization Protocol (FIP) Test Suite Version 1.0

Technical Document



Last Updated: April 23, 2010

Fibre Channel Consortium InterOperability Laboratory University of New Hampshire 121 Technology Drive, Suite 2 Durham, NH 03824 Phone: +1-603-862-0701 Fax: +1-603-862-4181

http://www.iol.unh.edu/consortiums/fc

### **Table of Contents**

Table of Contents	2
Acknowledgments	4
Introduction	5
Test Setup	8
Group 1: VLAN Discovery	
Test 7.1.1: ALL-FCF-MAC Group Address Listening	10
Test 7.1.2: FIP VLAN Request Frame Response	11
Test 7.1.3: Discarding Multicast FIP VLAN Request Frames with Duplicate MAC Addresses	12
Test 7.1.4: VLAN Configuration Change Response	13
Test 7.1.5: FIP VLAN Request Frame Response	14
Test 7.1.6: Discarding Multicast VLAN Request Frames with Duplicate MAC Addresses	15
Test 7.1.7: VLAN Configuration Change Response	16
Group 2: ENode/FCF Discovery	17
Test #7.2.1: DUT Transmits FIP Discovery Advertisements	18
Test #7.2.2: DUT Receives FIP Discovery Advertisement	19
Test #7.2.3: DUT Transmits FIP Discovery Solicitation	
Test #7.2.4: DUT Transmits FIP Discovery Solicitation upon Becoming Operational	21
Test #7.2.5: DUT Transmits FIP Discovery Advertisement after Receiving FIP Discovery Solicitation	22
Test #7.2.6: Max FCoE Size Descriptor in a FIP Discovery Solicitation	
Test #7.2.7: FIP Discovery Advertisement Pad Extension	
Test #7.2.8: DUT Discards Discovery Solicitation – DUT is ENode	25
Test #7.2.9: DUT Discards Discovery Solicitation – DUT is VF_Port Capable FCF-MAC	26
Test #7.2.10: DUT Discards Discovery Advertisement – Identical MAC Addresses	27
Group 3: FCF/FCF Discovery	
Test #7.3.1: Periodic Transmission of Multicast Discovery Advertisements	29
Test #7.3.2: Transmission of Unicast Discovery Solicitation	
Test #7.3.3: Transmission of Unicast Discovery Advertisement	
Test #7.3.4: Discarding Invalid Discovery Solicitations	32
Test #7.3.5: Discarding Invalid Discovery Advertisements	34
Group 4: VN_Port to VF_Port Virtual Link Instantiation	
Test #7.4.1: Fabric Login Using FIP Frames	
Test #7.4.2: Indication of Addressing Mode in Fabric Login	37
Test #7.4.3: Reception of FLOGI or NPIV FDISC by FCF	
Test #7.4.4: Explicit VN_Port to VF_Port Virtual Link De-Instantiation	39
Group 5: VE_Port to VE_Port Virtual Link Instantiation	40
Test #7.5.1: ELP Transmission.	
Group 6: Virtual Link Maintenance	
Test #7.6.1: Physical Layer Disconnect.	
Test #7.6.2: Transmission of FIP Keep Alive	
Test #7.6.3: Transmission of Discovery Advertisement.	
Test #7.6.4: Reception of a FIP Clear Virtual Links Frame	
Test #7.6.5: Transmission of FIP Clear Virtual Links Frame	
Test #7.6.6: Locally Modified FKA_ADV_PERIOD Value	48
Test #7.6.7: Remotely Modified FKA. ADV. PERIOD Value	49

### **Modification Record**

• April 23, 2010 – Version 1.0 Release

Dustin Schoenbrun: Original Document based off of FC-BB-5 rev 2.00 Standard

### Acknowledgments

The University of New Hampshire would like to acknowledge the efforts of the following individuals in the development of this test suite.

Dustin Schoenbrun University of New Hampshire
Adam Rozumek University of New Hampshire
Mikkel Hagen University of New Hampshire

### Introduction

#### Overview

The University of New Hampshire's InterOperability Laboratory (UNH-IOL) is an institution designed to improve the interoperability of standards based products by providing an environment where a product can be tested against other implementations of a standard. These tests are designed to determine if an FCoE product conforms to specifications defined in *Fibre Channel Backbone 5 (FC-BB-5) Rev 2.00 Standard T11/Project 1871-D* (hereafter refered to as "FC-BB-5"). This suite of tests has been developed to help implementers evaluate the functioning of their Fibre Channel over Ethernet-based products. The tests do not determine if a product conforms to the Fibre Channel standard, nor are they purely interoperability tests. Rather, they provide one method to isolate problems within a Fibre Channel device. Successful completion of all tests contained in this suite does not guarantee that the tested device will operate with other Fibre Channel devices. However, combined with satisfactory operation in the IOL's semi-production environment, these tests provide a reasonable level of confidence that the Device Under Test (DUT) will function well in most multivendor Fibre Channel Environments.

### **Organization of Tests**

The tests contained in this document are organized to simplify the identification of information related to a test and to facilitate in the actual testing process. Each test contains an identification section that describes the test and provides cross-reference information. The discussion section covers background information and specifies why the test is to be performed. Tests are grouped in order to reduce setup time in the lab environment. Each test contains the following information:

#### **Test Number**

The Test Number associated with each test follows a simple grouping structure. Listed first is the Clause followed by the Test Group Number followed by the test's number within the group. This allows for the addition of future tests to the appropriate groups of the test suite without requiring the renumbering of the subsequent tests.

### **Purpose**

The purpose is a brief statement outlining what the test attempts to achieve. The test is written at the functional level.

### References

This section specifies all reference material *external* to the test suite, including the specific subclauses references for the test in question, and any other references that might be helpful in understanding the test methodology and/or test results. External sources are always referenced by a bracketed number (e.g., [1]) when mentioned in the test description. Any other references in the test description that are not indicated in this manner refer to elements within the test suite document itself (e.g., "Appendix 6.A", or "Table 6.1.1-1")

### **Resource Requirements**

The requirements section specifies the test hardware and/or software needed to perform the test. This is generally expressed in terms of minimum requirements, however in some cases specific equipment manufacturer/model information may be provided.

### **Last Modification**

This specifies the date of the last modification to this test.

#### Discussion

The discussion covers the assumptions made in the design or implementation of the test, as well as known limitations. Other items specific to the test are covered here.

### Test Setup

The setup section describes in detail the configuration of the test environment and includes a block diagram for clarification as well as information such as the interconnection of devices, what monitoring equipment should capture, what the generation equipment should send, and any other configuration information vital to carrying out the test. Small changes in the configuration should be included in the test procedure.

#### **Procedure**

The procedure section of the test description contains the step-by-step instructions for carrying out the test. It provides a cookbook approach to testing, and will often be interspersed with observable results.

### **Observable Results**

The observable results section list observables that can be examined by the tester to verify that the DUT is operating properly. When multiple values are possible for an observable, this section provides a short discussion on how to interpret them. Note that complete delineation between the observables in the **Procedure** and **Observable** is virtually impossible. As such, a careful note should be made of the requirement in both sections. In certain cases, it may be necessary to modify certain steps in the **Procedure** section while doing the actual tests so as to be able to perform the tests. In such cases, the modifications will be noted in the summary report.

### **Possible Problems**

This section provides some troubleshooting procedures in the event that the test does not yield the expected results.

### Legend

For reasons of brevity, the following abbreviations are used within this test suite:

DUT Device Under Test

FCoE Fibre Channel over Ethernet FIP FCoE Initialization Protocol

TS Testing Station

In the test suite, state transitions have been described using the notations used in the FC-BB-5 document. Any underlined set of transitions implies that the transition is repeated continuously.

### References


The following documents are referenced in this text:

• ANSI X3T11/Project 1871-D/Rev. 2.00 Fibre Channel Backbone 5 FC-BB-5 (hereafter referred to as "FC-BB-5")

### **Test Setup**

The following test setup is used in this test suite:

Test Setup 1:



### **Group 1: VLAN Discovery**

**Overview:** This section tests the capability of the DUT when attempting to discover VLANs on the fabric. These tests are applicable to VN\_Ports, VF\_Ports, and VE\_Ports as they test the capabilities of all.

### Test 7.1.1: ALL-FCF-MAC Group Address Listening

**Purpose:** To verify that the DUT is listening to the All-FCF-MACs group address in the default VLAN and in other VLANs that ENodes or FCFs may use to invoke the protocol.

### **References:**

FC-BB-5 - Clause 7.8.2 - Page 94.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

FCF-MACs shall listen to the All-FCF-MACs group address in the default VLAN and in other VLANs that ENodes or FCFs may use to invoke the protocol.

**Test Setup:** *Test Setup 1*. Connect the Testing Station and DUT as shown.

### **Procedure:**

Part a: Default FCoE VLAN

- 1. The testing station is instructed to transmit a protocol-invoking frame to the All-FCF-MACs group address on the default VLAN that the DUT is configured for.
- 2. Traffic is monitored and captured.

### Part b: Non-Default FCoE-Enabled VLAN

- 1. The testing station is instructed to transmit a protocol-invoking frame to the All-FCF-MACs group address on a different, FCoE-Enabled VLAN other than the default VLAN enabled on the DUT.
- 2. Traffic is monitored and captured.

### Part c: Non-Default FCoE-Disabled VLAN

- 1. The testing station is instructed to transmit a protocol-invoking frame to the All-FCF-MACs group address on a different, FCoE-Disabled VLAN other than the default VLAN enabled on the DUT.
- 2. Traffic is monitored and captured.

### **Observable Results:**

Parts a and b: The DUT should respond to the All-FCF-MACs addressed frame.

Part c: The DUT should not respond to the All-FCF-MACs addressed frame.

### **Test 7.1.2: FIP VLAN Request Frame Response**

**Purpose:** To verify that, if the DUT is a VF\_Port capable FCF and receives a FIP VLAN request frame, it responds with a unicast FIP VLAN notification frame over the same VLAN.

#### **References:**

FC-BB-5 - Clause 7.8.2 - Page 93

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames.
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

An ENode MAC may send a FIP VLAN Request frame to the ALL\_FCF\_MACs MAC address over an available VLAN (e.g., the port VLAN). VF\_Port capable FCF-MACs that receive a FIP VLAN Request frame shall respond with a unicast FIP VLAN Notification frame over the same VLAN. *This test is applicable to VF\_Port capable FCF devices only.* 

**Test Setup:** *Test Setup 1.* Connect the Testing Station, DUT and the Monitor as shown.

### **Procedure:**

- 1. The testing station, acting as an ENode, is instructed to transmit a FIP VLAN Request frame to the DUT
- 2. The exchange between the DUT and the Testing Station is captured and observed.

### **Observable Results:**

On the Monitor, verify that the DUT responds to the FIP VLAN Request with a unicast FIP VLAN Notification frame over the same VLAN.

### **Test 7.1.3: Discarding Multicast FIP VLAN Request Frames with Duplicate MAC Addresses**

**Purpose:** To verify that the DUT discards any multicast FIP VLAN request frame that has a source address equal to its FCF-MAC address.

### **References:**

FC-BB-5 - Clause 7.8.2 - Page 93.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

A VF\_Port capable FCF-MAC shall discard a multicast FIP VLAN request frame that has a source address equal to its FCF\_MAC address, and the FIP VLAN request frame should be reported in a vendor specific way as an indication of a MAC address duplication. *This test is applicable to VF Port capable FCF devices only.* 

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown.

### **Procedure:**

- 1. The testing station is instructed to transmit a multicast FIP VLAN request frame that has a source address equal to the DUT's FCF-MAC address.
- 2. Traffic is monitored and captured.

### **Observable Results:**

The DUT should discard the frame and potentially report the frame in a vendor specific way.

### **Test 7.1.4: VLAN Configuration Change Response**

**Purpose:** To verify that the DUT, if it is VF\_Port capable, correctly constructs a FIP VLAN notification frame if it chooses to create one in response to a change in configuration of VLANs on which it supports FC-BB E services.

### **References:**

FC-BB-5 – Clause 7.8.2 – Page 93.

### **Resource Requirements:**

- A Testing Station capable of changing the settings on a VLAN where the DUT is supporting FC-BB\_E services.
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

If the configuration of VLANs on which a VF\_Port capable FCF-MAC supports FC-BB\_E services changes, that FCF-MAC should send a unicast FIP VLAN notification frame to each ENode MAC address with which that FCF-MAC has established VN\_Port to VF\_Port virtual links. The unicast FIP VLAN notification frame shall carry the revised list of VLAN IDs over which the originating VF\_Port capable FCF-MAC offers FC-BB\_E services. This test is applicable to VF\_Port capable FCF devices only.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown.

### **Procedure:**

- 1. Set up VLAN 5 on the FCoE switch to be able to handle FCoE traffic.
- 2. Change the FCoE enabled VLAN on the FCoE switch from 5 to 6.
- 3. Traffic is monitored and captured.

### **Observable Results:**

If the DUT sent any unicast FIP VLAN notification frames, it should carry the revised list of VLAN Ids over which the DUT supports FC-BB\_E services.

### **Test 7.1.5: FIP VLAN Request Frame Response**

**Purpose:** To verify that the DUT, if it is VF\_Port capable, responds to FIP VLAN request frames with a unicast FIP VLAN notification frame over the same VLAN.

#### **References:**

FC-BB-5 – Clause 7.8.2 – Page 93.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

A VE\_Port capable FCF-MAC may send a FIP VLAN request frame to the MAC address ALL-FCF-MACs over an available VLAN. VE\_Port capable FCF-MACs that receive a FIP VLAN request frame shall respond with a unicast FIP VLAN notification frame over the same VLAN. The FIP VLAN notification frame carries the list of VLAN IDs over which the originating FCF offers FC-BB\_E services. The VE\_Port capable FCF-MAC that received a FIP VLAN notification frame may enable one or more of these VLANs for subsequent operations. *This test is applicable to VE\_Port capable FCF devices only.* 

**Test Setup:** *Test Setup 1*. Connect the Testing Station and DUT as shown.

### **Procedure:**

- 1. The testing station is instructed to transmit a FIP VLAN request frame to the DUT
- 2. Traffic is monitored and captured.

### **Observable Results:**

The DUT should respond to the FIP VLAN request with a unicast FIP VLAN notification frame over the same VLAN.

### Test 7.1.6: Discarding Multicast VLAN Request Frames with Duplicate MAC Addresses

**Purpose:** To verify that the DUT discards any multicast VLAN request frame that has a source address equal to its FCF-MAC address.

#### **References:**

FC-BB-5 - Clause 7.8.2 - Page 94.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

A VF\_Port capable FCF-MAC shall discard a multicast VLAN request frame that has a source address equal to its FCF\_MAC address, and the VLAN request frame should be reported in a vendor specific way as an indication of a MAC address duplication. *This test is applicable to VF Port capable FCF devices only*.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown.

### **Procedure:**

- 1. The testing station is instructed to transmit a multicast VLAN request frame that has a source address equal to the DUT's FCF-MAC address.
- 2. Traffic is monitored and captured.

### **Observable Results:**

The DUT should discard the frame and potentially report the frame in a vendor specific way.

### **Test 7.1.7: VLAN Configuration Change Response**

**Purpose:** To verify that the DUT, if it is VE\_Port capable, correctly constructs a FIP VLAN notification frame if it chooses to create one in response to a change in configuration of VLANs on which it supports FC-BB E services.

### **References:**

FC-BB-5 – Clause 7.8.2 – Page 93.

### **Resource Requirements:**

- A Testing Station capable of changing the settings on a VLAN where the DUT is supporting FC-BB\_E services.
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

If the configuration of VLANs on which a VE\_Port capable FCF-MAC supports FC-BB\_E services changes, that FCF-MAC should send a unicast FIP VLAN notification frame to each FCF-MAC address with which that FCF-MAC has established VE\_Port to VE\_Port virtual links. The unicast FIP VLAN notification frame shall carry the revised list of VLAN IDs over which the originating VE\_Port capable FCF-MAC offers FC-BB\_E services. This is applicable to VE\_Port capable FCF devices only.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown.

### **Procedure:**

- 1. Change the settings on a VLAN where the DUT is supporting FC-BB\_E services.
- 2. Traffic is monitored and captured.

### **Observable Results:**

If the DUT sent any unicast FIP VLAN notification frames, it should carry the revised list of VLAN IDs over which the DUT supports FC-BB\_E services.

### **Group 2: ENode/FCF Discovery**

**Overview:** This section tests the capability of the DUT when attempting to discover other ENodes or FCFs on the fabric. These tests are applicable to both ENodes and FCFs as they test the capabilities of both.

### Test #7.2.1: DUT Transmits FIP Discovery Advertisements

Purpose: To verify that the DUT correctly transmits FIP Discovery Advertisements periodically.

### **References:**

FC-BB-5 – Clause 7.8.3.2 – Page 94 Ibid – Clause 7.8.7.3 – Page 116

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames.
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

The FCoE Controller of a VF\_Port capable FCF-MAC will periodically send multicast Discovery Advertisements to the All-ENode-MACs (01:10:18:01:00:01) group address every FKA\_ADV\_PERIOD (250-90000ms +/- 0 to 100ms). *This test is applicable to VF Port capable FCF devices only*.

**Test Setup:** *Test Setup 1.* Connect the Testing Station, DUT and the Monitor as shown. The DUT has not yet completed the FIP protocol and has not completed login.

### **Procedure:**

- 1. The DUT is instructed to start initialization using FIP.
- 2. The testing station is instructed not respond to the DUT for a period of time.
- 3. The exchange between the DUT and the Testing Station is captured and observed.

#### **Observable Results:**

On the Monitor, verify that the DUT sends FIP Discovery Advertisements every FKA\_ADV\_PERIOD and also verify that the DUT sets the maximum FCoE PDU size value within the Max FCoE Size descriptor that it intends to use for FCoE traffic.

Possible Problems: None.

18

### Test #7.2.2: DUT Receives FIP Discovery Advertisement

**Purpose:** To verify that the DUT correctly handles the reception of FIP Discovery Advertisements.

### **References:**

FC-BB-5 – Clause 7.8.3.2 – Page 94 Ibid – Table 27 – Page 104

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

The FCoE Controller of an ENode MAC, upon receiving FIP Discovery Advertisements, shall verify the VN\_Port addressing capabilities of the advertising FCF-MAC against its own VN\_Port addressing capabilities. If the advertising FCF-MAC is compatible, then the FCoE Controller of an ENode MAC shall create an entry for each such FCF-MAC in an internal FCF List. If the advertising FCF-MAC is incompatible, then the Discovery Advertisement shall be discarded. *This test is applicable to VN Port capable ENode devices*.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT has not completed FIP and has not logged in.

### **Procedure:**

Part d: FIP Discovery Advertisements are Compatible with the DUT

- 1. The DUT is instructed to start initialization using FIP
- 2. The Testing Station will send FIP Discovery Advertisements that are compatible with the capabilities of the DUT.

Part e: FIP Discovery Advertisements are NOT Compatible with the DUT

- 1. The DUT is instructed to start initialization using FIP
- 2. The Testing Station will send FIP Discovery Advertisements that are NOT compatible with the capabilities of the DUT.

### **Observable Results:**

Part a: The DUT should create an entry for the Testing Station in it's internal FCF List

Part b: The DUT should discard the FIP Discovery Advertisements and not add the Testing Station to it's internal FCF List.

### Test #7.2.3: DUT Transmits FIP Discovery Solicitation

**Purpose:** To verify that the DUT correctly transmits FIP Discovery Solicitations after receiving FIP Discovery Advertisements.

#### **References:**

FC-BB-5 - Clause 7.8.3.2 - Page 94

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

In order to perform a FIP FLOGI with an FCF\_MAC in the FCF Login Set with the 'Max FCoE Size Verified' flag set to zero, the FCoE Controller of an ENode MAC shall transmit a unicast Discovery Solicitation to that FCF-MAC address after receiving a Discovery Advertisement.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT has not completed FIP and has not logged in.

### **Procedure:**

- The testing station, acting as an FCF, is instructed to send a multicast Discovery Advertisement to the All-ENode-MACs group address.
- 2. Traffic is monitored and captured.

#### **Observable Results:**

The DUT should transmit a unicast FIP Discovery Solicitation to the Testing Station's MAC address.

### Test #7.2.4: DUT Transmits FIP Discovery Solicitation upon Becoming Operational

**Purpose:** To verify that the DUT correctly transmits a multicast FIP Discovery Solicitation to the All-FCF-MACs group address (01:10:18:01:00:02) upon becoming operational.

#### **References:**

FC-BB-5 – Clause 7.8.3.2 – Page 95.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

When the FCoE Controller of an ENode MAC becomes operational it should discover VF\_Port capable FCF-MACs with which it may perform FIP FLOGI by transmitting a multicast FIP Discovery Solicitation to the All-FCF-MACs group address (01:10:18:01:00:02).

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT has already logged in using FIP and is idle.

### **Procedure:**

- 1. Disconnect the fiber connecting the DUT and the Testing Station.
- 2. Reconnect the fiber
- 3. Monitor and Capture the traffic.

#### **Observable Results:**

The DUT should transmit a multicast FIP Discovery Solicitation to the All-FCF-MACs group address upon becoming operational.

### Test #7.2.5: DUT Transmits FIP Discovery Advertisement after Receiving FIP Discovery Solicitation

**Purpose:** To verify that the DUT, upon receiving a FIP Discovery Solicitation, transmits a solicited unicast FIP Discovery Advertisement to the soliciting ENode MAC.

### **References:**

```
FC-BB-5 – Clause 7.8.3.2 – Page 95. Ibid – Table 47 – Page 122.
```

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

When a VF\_Port capable FCF-MAC receives a FIP Discovery Solicitation from an ENode MAC with which the VN\_Port addressing modes are compatible and if it is configured to allow a FIP FLOGI from that ENode, it shall transmit a solicited unicast FIP Discovery Advertisement to that ENode MAC within ADV\_TOV (2 seconds) time. This test is applicable to VF\_Port capable FCF devices.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT has not completed FIP and has not logged in.

### **Procedure:**

- 1. The testing station is instructed to send a FIP Discovery Solicitation to the DUT.
- 2. Traffic is monitored and captured.

#### **Observable Results:**

The DUT should transmit a solicited unicast FIP Discovery Advertisement to the Testing Station within AD\_TOV (2 seconds) time.

### Test #7.2.6: Max FCoE Size Descriptor in a FIP Discovery Solicitation

**Purpose:** To verify that when the DUT transmits a FIP Discovery Solicitation it sets the value of the maximum FCoE PDU Size.

#### **References:**

FC-BB-5 – Clause 7.8.3.2 – Page 95.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When either a ENode MAC or a VE\_Port capable FCF-MAC transmits a FIP Discovery Solicitation, it shall specify the maximum FCoE PDU size that it intends to use for FCoE traffic within the Max FCoE Size Descriptor

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT has not completed FIP and has not logged in.

### **Procedure:**

- 1. The testing station is instructed to start initialization using FIP.
- 2. Traffic is monitored and captured.

### **Observable Results:**

The DUT should transmit a solicited unicast FIP Discovery Solicitation to the Testing Station within AD\_TOV (2 seconds) time with the Max FCoE Size Descriptor field filled in with the maximum FCoE PDU size that it intends to use for FCoE traffic.

### Test #7.2.7: FIP Discovery Advertisement Pad Extension

**Purpose:** To verify that the DUT, after receiving a FIP Discovery Solicitation, will respond with a FIP Discovery Advertisement with a padded length of the Max FCoE Size specified in the FIP Discovery Solicitation.

#### **References:**

FC-BB-5 – Clause 7.8.3.2 – Page 95.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When either a ENode MAC or a VE\_Port capable FCF-MAC transmits a FIP Discovery Advertisement in response to a FIP Discovery Solicitation, it shall be padded out to the length specified in the Max FCoE Size descriptor in the FIP Discovery Solicitation.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT has not completed FIP and has not logged in.

### **Procedure:**

- 1. The testing station is instructed to send a FIP Discovery Solicitation to the DUT with the Max FCoE Size Descriptor value set to 512 bytes.
- 2. Traffic is monitored and captured.
- 3. Repeat steps 1 and 2 with the Max FCoE Size Descriptor value set to 1500 bytes and 2500 bytes.

### **Observable Results:**

The DUT should transmit a solicited unicast FIP Discovery Advertisement to the Testing Station within AD\_TOV (2 seconds) time with the frame padded out to the value specified in the Testing Station's Max FCoE Size Descriptor.

### Test #7.2.8: DUT Discards Discovery Solicitation – DUT is ENode

Purpose: To verify that the DUT discards any received Discovery Solicitation.

### **References:**

FC-BB-5 – Clause 7.8.3.2 – Page 96.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

When an ENode MAC receives any type of Discovery Solicitation, it shall discard it. This test is only applicable to ENodes.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT has not completed FIP and has not logged in.

### **Procedure:**

- 1. The testing station is instructed to send a FIP Discovery Solicitation to the DUT.
- 2. Traffic is monitored and captured.

### **Observable Results:**

The DUT should not respond to the FIP Discovery Solicitation transmitted by the Testing Station.

### Test #7.2.9: DUT Discards Discovery Solicitation – DUT is VF Port Capable FCF-MAC

**Purpose:** To verify that the DUT discards any Discovery Solicitation originated by a VE\_Port capable FCF-MAC as well as discards any Discovery Solicitation that has a source address equal to its FCF-MAC address.

#### **References:**

FC-BB-5 – Clause 7.8.3.2 – Page 96.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When a VF\_Port capable FCF-MAC receives a Discovery Solicitation from a VE\_Port capable FCF-MAC it shall discard it. Also, when it receives a Discovery Solicitation that has a source address that is equal to its own FCF-MAC address it shall discard it and report it in a vendor specific way. *This test is only applicable to VF\_Port Capable FCF-MAC devices*.

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT has not completed FIP and has not logged in.

### **Procedure:**

### Part A:

- 1. The testing station, acting as a VE\_Port capable FCF-MAC, is instructed to transmit a Discovery Solicitation to the DUT.
- 2. Traffic is monitored and observed.

### Part B:

- 1. The testing station is instructed to transmit a Discovery Solicitation with the source address equal to the FCF-MAC address of the DUT.
- 2. Traffic is monitored and captured.

### **Observable Results:**

The DUT should not respond to the FIP Discovery Solicitation transmitted by the Testing Station.

### **Test #7.2.10: DUT Discards Discovery Advertisement – Identical MAC Addresses**

Purpose: To verify that the DUT discards any Discovery Advertisement with a source address equal to its own.

### **References:**

FC-BB-5 – Clause 7.8.3.2 – Page 96.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

When an ENode MAC receives an unsolicited multicast Discovery Advertisement that has a source address equal to its ENode MAC address it shall discard it.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT has not completed FIP and has not logged in.

### **Procedure:**

- 1. The testing station is instructed to send an unsolicited multicast Discovery Advertisement to the DUT.
- 2. Traffic is monitored and captured.

### **Observable Results:**

The DUT should not respond to the Discovery Advertisement transmitted by the Testing Station.

### **Group 3: FCF/FCF Discovery**

**Overview:** The following tests exercise the DUT's ability to discover other FCFs on the network. These tests only apply to devices that act as FCFs.

### Test #7.3.1: Periodic Transmission of Multicast Discovery Advertisements

**Purpose:** To verify that the DUT periodically transmits multicast Discovery Advertisements to the All-FCF-MACs group address.

### **References:**

FC-BB-5 – Clause 7.8.3.3 – Page 96.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

The FCoE Controller of a VF\_Port capable FCF-MAC shall periodically transmit multicast Discovery Advertisements to the All-FCF-MACs group address (01:10:18:01:00:02) every FKA\_ADV\_PERIOD (250-90000 milliseconds, default is 8000).

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and can be in any state.

### **Procedure:**

1. Traffic is monitored and captured.

### **Observable Results:**

The DUT should transmit a multicast Discovery Advertisement to the All-FCF-MACs group address every FKA ADV PERIOD.

### Test #7.3.2: Transmission of Unicast Discovery Solicitation

**Purpose:** To verify that the DUT transmits a unicast Discovery Solicitation to an FCF-MAC that it wishes to perform FIP ELP with.

#### **References:**

FC-BB-5 – Clause 7.8.3.3 – Page 96.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

In order to perform FIP ELP with an FCF-MAC in the DUT's FCF list, it must have it's "Max FCoE Size Verified" flag set to one. In order to perform FIP ELP with an FCF-MAC with this flag set to zero, the DUT shall transmit a unicast Discovery Solicitation to that FCF-MAC address.

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

### **Procedure:**

- 1. The testing station is instructed to periodically transmit multicast Discovery Advertisements so that the DUT can add it to its internal FCF list.
- 2. Traffic is monitored and captured.

#### **Observable Results:**

The DUT should transmit a unicast Discovery Solicitation to the testing station.

### Test #7.3.3: Transmission of Unicast Discovery Advertisement

**Purpose:** To verify that the DUT transmits a solicited unicast Discovery Advertisement in response to a unicast Discovery Solicitation.

#### **References:**

FC-BB-5 – Clause 7.8.3.3 – Page 97.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

After receiving a unicast Discovery Solicitation from an FCF-MAC that wants to log in to the DUT, the DUT shall transmit a solicited unicast Discovery Advertisement to the FCF-MAC.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

### **Procedure:**

- Part A: Unicast Discovery Solicitation
  - 1. The testing station is instructed to transmit a unicast Discovery Solicitation to the DUT.
  - 2. Traffic is monitored and captured.

Part B: Multicast Discovery Solicitation

- 1. The testing station is instructed to transmit a multicast Discovery Solicitation to the All-FCF-MACs group address.
- 2. Traffic is monitored and captured.

### **Observable Results:**

Parts A and B: The DUT should transmit a solicited unicast Discovery Advertisement to the FCF-MAC address of the testing station within ADV\_TOV (2 seconds).

### Test #7.3.4: Discarding Invalid Discovery Solicitations

Purpose: To verify that the DUT discards invalid Discovery Solicitations from an FCF.

### **References:**

FC-BB-5 – Clause 7.8.3.3 – Page 97-98.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

After receiving a Discovery Solicitation from an FCF, an FCF-MAC shall perform the following verification checks:

- The Name\_Identifier field in the Discovery Solicitation shall be different than the Switch\_Name of the recipient FCF; and
- II. either
  - A. The FP bit is set to one and the FC-MAP value in the FC-MAP descriptor in the Discovery Solicitation shall be the same as the FC-MAP value of the recipient FCF; or
  - B. The FP bit is set to zero and the SP bit is set to one, and the FC-MAP value in the FC-MAP descriptor in the Discovery Solicitation shall be zero.

If any of the verification checks is false, then that Discovery Solicitation shall be discarded.

**Test Setup:** *Test Setup 1*. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

### **Procedure:**

Part A: Name Identifier Field Value is the Same as the Switch Name of the DUT

- 1. The testing station, acting as an FCF, transmits a Discovery Solicitation with the Name\_Identifier field equal to the DUT's Switch Name.
- 2. Traffic is monitored and captured.

Part B: FP Bit is set to one, FC-MAP value in the FC-MAP descriptor is different that the FC-MAP of the DUT

- 1. The testing station, acting as an FCF, transmits a Discovery Solicitation with the FP bit set to one and the FC-MAP value in the FC-MAP descriptor in the Discovery Solicitation is different than the FC-MAP value of the DUT.
- 2. Traffic is monitored and captured.

Part C: FP Bit is set to zero, SP bit is set to one. FC-MAP value in the FC-MAP descriptor is not zero

- 1. The testing station, acting as an FCF, transmits a Discovery Solicitation with the FP bit set to zero and the SP bit set to one and the FC-MAP value in the FC-MAP descriptor in the Discovery Solicitation is not equal to zero.
- 2. Traffic is monitored and captured.

Part D: Testing Station as an ENode transmits a Discovery Solicitation (applicable only to VE\_Port capable FCF-MACs)

- 1. The testing station, acting as an ENode, transmits a Discovery Solicitation to the DUT.
- 2. Traffic is monitored and captured.

### **Observable Results:**

Parts A, B, C and D: The DUT should discard the Discovery Solicitation transmitted by the testing station.

### **Test #7.3.5: Discarding Invalid Discovery Advertisements**

**Purpose:** To verify that the DUT discards invalid Discovery Advertisements from an FCF.

### **References:**

FC-BB-5 – Clause 7.8.3.3 – Page 98.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

After receiving a Discovery Advertisement, an FCF-MAC shall perform the following verification checks:

- I. The Name\_Identifier field value in the Discovery Advertisement shall be different than the Switch\_Name of the recipient FCF; and
- II. either
  - A. The FP bit is set to one and the FC-MAP value in the Fabric descriptor in the Discovery Advertisement shall be the same as the FC-MAP value of the recipient FCF; or
  - B. The FP bit is set to zero and the SP bit is set to one, and the FC-MAP value in the Fabric descriptor in the Discovery Advertisement shall be zero.

If any of the verification checks is false, then that Discovery Advertisement shall be discarded.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

#### **Procedure:**

- Part A: Name Identifier Field Value is the Same as the Switch Name of the DUT
  - 1. The testing station, acting as an FCF, transmits a Discovery Advertisement with the Name\_Identifier field equal to the DUT's Switch Name.
  - 2. Traffic is monitored and captured.
- Part B: FP Bit is set to one, FC-MAP value in the Fabric descriptor is different that the FC-MAP of the DUT
  - 1. The testing station, acting as an FCF, transmits a Discovery Advertisement with the FP bit set to one and the FC-MAP value in the Fabric descriptor in the Discovery Advertisement is different than the FC-MAP value of the DUT.
  - 2. Traffic is monitored and captured.
- Part C: FP Bit is set to zero, SP bit is set to one. Fabric value in the FC-MAP descriptor is not zero
  - 1. The testing station, acting as an FCF, transmits a Discovery Advertisement with the FP bit set to zero and the SP bit set to one and the FC-MAP value in the Fabric descriptor in the Discovery Advertisement is not equal to zero.
  - 2. Traffic is monitored and captured.

### **Observable Results:**

Parts A, B, and C: The DUT should discard the Discovery Advertisement transmitted by the testing station.

# Group 4: VN\_Port to VF\_Port Virtual Link Instantiation

Overview: The following tests exercise the DUT's ability to instantiate VN\_Port to VF\_Port virtual links. These tests apply to both VN\_Port and VF\_Port capable devices as these tests examine the capabilities of both.

### Test #7.4.1: Fabric Login Using FIP Frames

Purpose: To verify that the DUT during fabric login (i.e. FLOGI, NPIV FDISC) uses FIP frames to do so.

### **References:**

FC-BB-5 - Clause 7.8.4.1 - Page 98.

### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

### **Discussion:**

Fabric login (i.e. FLOGI, NPIV FDISC) shall be performed using FIP Frames and the associated FIP descriptor type (7 for an FLOGI, 8 for an NPIV FDISC).

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

### **Procedure:**

- 1. The Testing Station is instructed wait for the DUT to log into it using FIP.
- 2. The DUT is expected to then proceed into preforming Fabric login.
- 3. Traffic is monitored and captured.

### **Observable Results:**

The DUT should transmit an FLOGI or NPIV FDISC encapsulated within a FIP frame. The FIP frame should also have the FIP Descriptor type set to the appropriate value (7 for an FLOGI, 8 for an NPIV FDISC).

### Test #7.4.2: Indication of Addressing Mode in Fabric Login

**Purpose:** To verify that the DUT specifies the addressing mode that it intends to use when it transmits a FIP FLOGI or a FIP NPIV FDISC during Fabric login.

#### **References:**

FC-BB-5 – Clause 7.8.4.1 – Page 98.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When the FCoE Controller of an ENode MAC transmits a FIP FLOGI Request or a FIP NPIV FDISC Request it shall indicate the addressing mode it intends to use. It does this by specifying either the FP bit (for FPMA), the SP bit (for SPMA), or both. *This test is applicable to ENode devices only.* 

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

#### **Procedure:**

- 1. The Testing Station is instructed wait for the DUT to log into it using FIP.
- 2. The DUT is expected to then proceed into preforming Fabric login.
- 3. Traffic is monitored and captured.

#### **Observable Results:**

Within the FLOGI or NPIV FDISC encapsulated frames, verify that either the FP bit is set (for FPMA), the SP bit is set (for SPMA), or both are set.

Possible Problems: None.

37

### Test #7.4.3: Reception of FLOGI or NPIV FDISC by FCF

**Purpose:** To verify that the DUT handles the addressing modes specified by the received FLOGI or NPIV FDISC correctly.

#### **References:**

FC-BB-5 – Clause 7.8.4.1 – Page 99.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

### Last Updated: April 23, 2010

#### **Discussion:**

When the FCF receives FLOGI or NPIV FDISC frames, it has to determine which addressing mode the link partner wishes to use. These modes can be FPMA (Fabric-Provided MAC Address), SPMA (Server-Provided MAC Address), or both. *This test is applicable to FCFs only.* 

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

#### **Procedure:**

Part A: SP Bit is set to one, FP Bit is set to zero

- 1. The testing station is instructed to log into the DUT using FIP.
- 2. Upon receiving the solicited Discovery Advertisement from the DUT, the testing station is instructed to send an FLOGI with the SP Bit set to one and the FP Bit to zero.
- 3. Traffic is monitored and captured.

Part B: SP Bit is set to zero, FP Bit is set to one

- 1. The testing station is instructed to log into the DUT using FIP.
- 2. Upon receiving the solicited Discovery Advertisement from the DUT, the testing station is instructed to send an FLOGI with the SP Bit set to zero and the FP Bit to one.
- 3. Traffic is monitored and captured.

Part C: Both SP and FP Bits are set to one

- 1. The testing station is instructed to log into the DUT using FIP.
- 2. Upon receiving the solicited Discovery Advertisement from the DUT, the testing station is instructed to send an FLOGI with both the SP and FP Bits set to one.
- 3. Traffic is monitored and captured.

#### **Observable Results:**

- Part A: Verify that the DUT returns the MAC address specified in the FLOGI frame in it's LS ACC frame.
- Part B: Verify that the DUT returns a properly formed FPMA MAC address in it's LS\_ACC frame.
- Part C: Verify that the DUT selects one of the addressing modes and returns a MAC address for the selected addressing mode.

### Test #7.4.4: Explicit VN Port to VF Port Virtual Link De-Instantiation

**Purpose:** To verify that the DUT when explicitly de-instantiating a VN\_Port to VF\_Port Virtual Link it transmits a FIP-encapsulated Fabric LOGO frame.

#### **References:**

FC-BB-5 – Clause 7.8.4.1 – Page 99.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When the DUT wants to explicitly de-instantiate a VN\_Port to VF\_Port Virtual Link, it shall send a LOGO frame encapsulated within a FIP frame and set the FIP descriptor type field to the correct type (9 for LOGO). *This test is applicable to ENode devices only.* 

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

#### **Procedure:**

- 1. The DUT is instructed to log into the testing station.
- 2. After receiving the LS\_ACC from the testing station, the DUT is instructed to perform a Fabric Logout using a FIP-encapsulated LOGO frame.
- 3. Traffic is monitored and captured.

### **Observable Results:**

Verify that the LOGO frame is encapsulated within a FIP frame and verify that the FIP descriptor type for the LOGO frame is set to 9.

# Group 5: VE\_Port to VE\_Port Virtual Link Instantiation

Overview: The following tests exercise the DUT's ability to instantiate VE\_Port to VE\_Port Virtual Links using FIP. These tests are applicable to VE\_Port capable devices only.

### **Test #7.5.1: ELP Transmission**

**Purpose:** To verify that when the DUT wants to instantiate a VE\_Port to VE\_Port virtual link, it sends an ELP Request encapsulated within a FIP frame.

#### **References:**

FC-BB-5 – Clause 7.8.4.2 – Page 99.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When the DUT wants to instantiate a VE\_Port to VE\_Port virtual link, it shall send an ELP Request encapsulated within a FIP frame and shall set the FIP descriptor type field to 10.

**Test Setup:** *Test Setup 1.* Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

#### **Procedure:**

- 1. The DUT is instructed to log into the testing station.
- 2. After receiving the solicited Discovery Advertisement from the testing station, the DUT is instructed to transmit an ELP Request encapsulated within a FIP frame.
- 3. Traffic is monitored and captured.

#### **Observable Results:**

Verify that the ELP Request is encapsulated within a FIP frame and verify that the FIP descriptor type field is set to 10.

## **Group 6: Virtual Link Maintenance**

Overview: The following tests exercise the DUT's ability to maintain virtual links. The tests cover dealing with physical layer faults (both local and non-local), keeping the link alive, and other maintenance activities.

### Test #7.6.1: Physical Layer Disconnect

**Purpose:** To verify that when the physical layer of the DUT becomes non-operational it will de-instantiate all of its links.

#### **References:**

FC-BB-5 – Clause 7.8.5.2 – Page 99. Ibid. - Clause 7.8.5.3 – Page 101

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When the DUT detects that its physical layer is not operational it shall de-instantiate all its VN\_Port to VF\_Port virtual links if the DUT is an ENode MAC, or de-instantiate all of its VF\_Ports if the DUT is a VF\_Port capable FCF-MAC.

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

#### **Procedure:**

- 1. The DUT is instructed to log into the testing station and set up a virtual link.
- 2. The fiber connecting the DUT and the testing station is disconnected.
- 3. Traffic is monitored and captured.

#### **Observable Results:**

Verify that after the fiber is disconnected that the DUT de-instantiated all of its VN\_Port to VF\_Port virtual links if the DUT is an ENode MAC or that the DUT de-instantiated all of its VF\_Ports if DUT is a VF\_Port capable FCF-MAC.

### **Test #7.6.2: Transmission of FIP Keep Alive**

Purpose: To verify that the DUT occasionally transmits FIP Keep Alive frames to keep the virtual link active.

#### **References:**

FC-BB-5 – Clause 7.8.5.2 – Page 100.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

The FCoE Controller of an ENode MAC shall occasionally transmit a unicast FIP Keep Alive frame to the VF\_Port capable FCF-MAC that it has VN\_Ports logged in. It shall transmit the FIP Keep Alive frames every FKA\_ADV\_PERIOD (default value of 8000 milliseconds) if transmitting on behalf of the ENode MAC (i.e. without a Vx-Port Identification descriptor) or every FKA\_VN\_PERIOD (90 seconds) if transmitting on behalf of each VN Port associated with that ENode MAC.

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

#### **Procedure:**

- 1. The DUT is instructed to log into the testing station and set up a virtual link.
- 2. Traffic is monitored and captured for five minutes.

#### **Observable Results:**

Verify that the DUT periodically sends FIP Keep Alive frames every FKA\_ADV\_PERIOD (default value of 8000 milliseconds) if transmitting on behalf of the ENode MAC or every FKA\_VN\_PERIOD (90 seconds) if transmitting on behalf of each VN\_Port associated with that ENode MAC.

**Possible Problems:** It is possible that this behavior can be administratively disabled on the DUT. If this is the case, the DUT will not transmit FIP Keep Alive frames.

### Test #7.6.3: Transmission of Discovery Advertisement

**Purpose:** To verify that the DUT occasionally transmits unsolicited multicast Discovery Advertisements to keep the virtual link active.

#### **References:**

FC-BB-5 – Clause 7.8.5.2 – Page 100.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

The FCoE controller of an ENode MAC monitors the status of a VF\_Port with which it has VN\_Ports logged in by verifying reception of unsolicited multicast Discovery Advertisements from that VF\_Port. As a result, to keep the virtual link active, the VF\_Port shall transmit an unsolicited multicast Discovery Advertisement every FKA ADV PERIOD (default value of 8000 milliseconds).

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has not logged in.

#### **Procedure:**

- 1. The DUT is instructed to log into the testing station and set up a virtual link.
- 2. Traffic is monitored and captured for five minutes.

#### **Observable Results:**

Verify that the DUT periodically sends unsolicited multicast Discovery Advertisements every FKA\_ADV\_PERIOD (default value of 8000 milliseconds).

### Test #7.6.4: Reception of a FIP Clear Virtual Links Frame

Purpose: To verify that the DUT correctly handles the reception of a FIP Clear Virtual Links frame.

#### **References:**

FC-BB-5 – Clause 7.8.5.2 – Page 100.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When an ENode MAC receives a FIP Clear Virtual Link frame, it shall de-instantiate the VN\_Ports listed within the frame.

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has logged in.

### **Procedure:**

- 1. The Testing Station is instructed to send a FIP Clear Virtual Link frame specifying a VN\_Ports to be deinstantiated.
- 2. Traffic is monitored and captured.

#### **Observable Results:**

Verify that the DUT de-instantiates the specified VN\_Port upon the reception of the FIP Clear Virtual Link frame.

### Test #7.6.5: Transmission of FIP Clear Virtual Links Frame

Purpose: To verify that the DUT correctly transmits FIP Clear Virtual Links Frames at the appropriate times.

#### **References:**

FC-BB-5 – Clause 7.8.5.2 – Page 101.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When the FCoE Controller of a VF\_Port capable FCF-MAC receives a VN\_Port FIP Keep Alive from a VN\_Port that is not logged in it shall send a FIP Clear Virtual Links frame listing that VN\_Port. In addition, the FIP Clear Virtual Links frame shall not exceed the standard Ethernet MAC Client Data size (1500 bytes for basic frames, 1504 bytes for Q-tagged frames). If the list of VN\_Ports to be removed does not fit in one FIP frame, multiple FIP frames should be used to convey the entire list.

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has logged in

#### **Procedure:**

Part A: FIP Keep Alive from a VN Port that is not Logged In

- 1. The Testing Station is instructed to send a FIP Keep Alive claiming to be from a ENode that is not logged into the DUT.
- 2. The DUT should send a FIP Clear Virtual Links frame specifying the ENode that the Testing Station used.
- 3. Traffic is monitored and captured.

Part B: FIP Keep Alive from an ENode that is not Logged In

- 1. The Testing Station is instructed to send a FIP Keep Alive claiming to be from an ENode that is not logged into the DUT.
- 2. The DUT should send a FIP Clear Virtual Links frame listing no VN Ports.
- 3. Traffic is monitored and captured.

#### **Observable Results:**

Verify that the DUT transmits a FIP Clear Virtual Links frame to both the VN\_Port and the ENode that were listed by the Testing Station and that the FIP Clear Virtual Links frame does not exceed Ethernet frame size limits.

### Test #7.6.6: Locally Modified FKA ADV PERIOD Value

Purpose: To verify that the DUT correctly handles changes to the FKA ADV PERIOD value locally.

#### **References:**

FC-BB-5 – Clause 7.8.5.2 – Page 101.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

When the FKA\_ADV\_PERIOD value is decreased, a VF\_Port capable FCF-MAC shall transmit unsolicited multicast Discovery Advertisements at the interval specified value, but shall not use the new value for detection of missing ENode FIP Keep Alives until five times the old value has elapsed since the first updated unsolicited multicast Discovery Advertisement. When the FKA\_ADV\_PERIOD value is increased, a VF\_Port capable FCF-MAC shall transmit unsolicited multicast Discovery Advertisements at the interval specified by the old value until five times the old value has elapsed since the first updated Discovery Advertisement was transmitted. This test is applicable to devices that can change the FKA\_ADV\_PERIOD value.

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has logged in.

#### Procedure:

Part A: FKA ADV PERIOD Decreased

- 1. The FKA ADV PERIOD value on the DUT is decreased from its current value.
- 2. Traffic is monitored and captured for at least five times the previous FKA ADV PERIOD value.

Part B: FKA ADV PERIOD Increased

- 1. Tthe FkA ADV PERIOD value on the DUT is increased from its current value.
- 2. Traffic is monitored and captured for at least five times the previous FKA\_ADV\_PERIOD value.

#### **Observable Results:**

Verify that after five times the old FKA\_ADV\_PERIOD the device starts using the new value for FKA\_ADV\_PERIOD. Also verify that the updated value is shown in the subsequent Discovery Advertisements.

### Test #7.6.7: Remotely Modified FKA ADV PERIOD Value

Purpose: To verify that the DUT correctly handles changes to the FKA\_ADV\_PERIOD value remotely.

#### **References:**

FC-BB-5 – Clause 7.8.5.2 – Page 101.

#### **Resource Requirements:**

- A Testing Station capable of transmitting user-defined FCoE Frames
- A Monitor capable of capturing FCoE traffic.

Last Updated: April 23, 2010

#### **Discussion:**

On detecting an updated FKA\_ADV\_PERIOD value, an ENode shall transmit ENode FIP Keep Alive frames at the updated FKA\_ADV\_PERIOD value as well as use this value to detect missing Discovery Advertisements.

**Test Setup:** Test Setup 1. Connect the Testing Station and DUT as shown. The DUT is powered on and has logged in.

#### **Procedure:**

- 1. The testing station is instructed to change its FKA\_ADV\_PERIOD value and send out an unsolicited multicast Discovery Advertisement with the new value.
- 2. The testing station is instructed to stop sending periodic unsolicited multicast Discovery Advertisements so that the link will time out.
- 3. Traffic is monitored and captured.

#### **Observable Results:**

Verify that the DUT sends its FIP Keep Alive frames at the new interval specified by the testing station. Also verify that the DUT uses the new value to detect the lack of unsolicited multicast Discovery Advertisements.